

Highover Farm, Hitchin
Open Space Management & Maintenance
Plan (*non BNG elements*)
Phase: 1

Client: BDW North Thames

12th May 2026 – Issue 3



Report Issue 1: DATE: 03/06/2025 Status: INITIAL ISSUE
Report Issue 2: DATE: 02/03/2026 Status: PLANNING
Report Issue 3: DATE: 12/05/2026 Status: PLANNING

Author: Alex Luck CMLI
Author: Alex Luck CMLI
Author: Alex Luck CMLI

Golby + Luck Ltd

Midlands

Wilson House
207 Leicester Road
Ilstock
Leicestershire
LE67 6HP

York

Suite 2.2
Innovation Centre
Innovation Way
York
YO10 5NY

t: 01530 265688

e: info@golbyandluck.co.uk

w: www.golbyandluck.co.uk





CONTENTS

1 MANAGEMENT OPERATIONS..... 1

2 MANAGEMENT SCHEME REVIEW & MAINTENANCE SCHEDULES 8

APPENDIX A – Phase 1 On-plot Landscape Proposals - GL2024 LP 10-12 Rev E & GL2024 LP 13-14 Rev D

Phase 1 POS Landscape Proposals – GL2024 LP 15-18 Rev B & 19 Rev A



1 MANAGEMENT OPERATIONS

Introduction

- 1.1 This Phase 1, Open Space Management & Maintenance Plan has been prepared by Golby + Luck Landscape Architects on behalf of BDW North Thames for their site at Higlover Farm, Hitchin. It has been produced in association with the Outline Landscape and Environmental Management Plan (OLEMP) Version: Vf1, dated 29th April 2026 which sets out the overarching maintenance principles for the whole site, and the Phase 1 LEMP, Version: Vf1, dated 29th April 2026 which provides the specific detail for Phase 1 reserved matters, both prepared by Ecology Solutions. All three documents should be read in conjunction with one another
- 1.2 This report specifically relates to the Phase 1 Residential Reserved Matters Application (App no.25/02794/RM) and seeks to partially discharge (Phase 1) Planning Condition 13 of the approved outline planning permission (Ref: 18/01154/OP), which states:

Prior to or concurrent with the first reserved matters submitted in each phase identified in Condition 5 Phasing and Delivery a detailed Open Space Management and Maintenance Scheme for the management and maintenance of all areas of open space (to include parks, greenways, allotments, play areas, informal open space, semi-natural green space, public squares) shall be submitted to and agreed in writing by the Local Planning Authority and implemented in accordance with an agreed timetable and approved phasing strategy. Details to be submitted shall include:

- a) Details of landscape management and maintenance plans;*
- b) Details of planting, grass cutting, weeding and pruning;*
- c) Management of sustainable urban drainage features;*
- d) Management of biodiversity enhancements;*
- e) Inspection, repair and maintenance of all hard landscaping and structures;*
- f) Management, monitoring and operational restrictions; and*
- g) Maintenance and planting replacement programme for the establishment period of landscaping.*



The open spaces provided shall be retained for their intended purpose and in accordance with the approved management plan unless otherwise agreed in writing by the local planning authority.

Reason: To ensure adequate open space and amenity provision as per North Hertfordshire Local Plan Policy NE6.

- 1.3 This Open Space Management & Maintenance Plan deals with the non-ecological maintenance elements (BNG) found within the public open space network, not covered by the Phase 1 LEMP, but that require consideration to deliver a successful public open space network. This document provides a comprehensive schedule of maintenance operations covering both annual maintenance activities and the long-term management of the proposed open spaces.
- 1.4 The Management Entity responsible for the implementation of the OLEMP, associated LEMPS and Open Space Management will either be North Hertfordshire District Council (NHDC) or a Management Company (ManCo) appointed by BDW Trading Ltd. The S106 Agreement allows the NHDC to approve the funding and management regime.
- 1.5 In the case of the Management Entity being NHDC, the funding mechanism will be through monies paid by the developer to NHDC.
- 1.6 The S106 at Schedule 2 Part 2 clause 14.6 requires the developer to submit an open space management calculation and amount of maintenance contribution on a phased/reserved matter basis, and clause 14.12 to pay the contribution for that phase/reserved matter prior to the commencement of said phase/reserved matter.
- 1.7 In the case of the Management Entity being a ManCo, the ManCo will be adequately self-funded or through on-going arrangements which may include the levy of a service charge on each individual dwelling (and may also comprise a resident management company entity).
- 1.8 The Open Space Management & Maintenance Plan is an evolving plan. During the course of the development at Highover Farm the plan will be updated and supplemented as more of the phases of the development associated with the wider site are designed and delivered.
- 1.9 The initial landscape contract will include 12 months maintenance and defect liability period. Following the initial 12-month maintenance defect liability period the landscape



areas will be covered by the approved Contractor who will take responsibility for all hard and soft landscape elements on a running contract managed by the appointed Management Entity. This plan will run in perpetuity and will be reviewed at 5 year intervals so that operations can be adapted to the development of the landscaping scheme.

1.10 The overall objectives for this management plan are:

- To establish a multi-functional and attractive public open space network that contributes to the visual amenity of the site and enjoyment by users;
- To ensure best horticultural, environmental and health and safety practices at all times;
- To ensure that methods employed respect and encourage wildlife and promote climate resilience; and
- To ensure defects in the landscape are identified early and addressed promptly.

1.11 This document should be read in conjunction with the latest revision of the site landscape proposals, see **Appendix A**. This drawing details all existing and proposed habitats.

Insurances and Certification

1.12 The appointed Contractor must provide details of all necessary insurances and certification to carry-out the works specified in this management plan. It is the responsibility of the Management Entity to ensure that all submitted insurances and certificates are up to date and provide the appropriate level of cover for the specified works.

Landscape Operations

1.13 The following sets out the landscape components that are considered in detail in this management plan:

- Litter and debris removal;
- SUDS maintenance;
- Hard landscape and site furniture maintenance; and
- Children's play area.

Environmental Considerations

1.14 All chemical weed control must be carried out by suitably trained staff in accordance with the manufacturers recommendations and the legislation set out below:

- The Food and Environment Protection Act (1985);
- The Control of Pesticides Regulations 1986 (COPR) (as amended 1997);



- The Control of Substances Hazardous to Health Regulations (2002);
- The Environment Protection Act (1990)

- 1.15 It is the Contractors responsibility to ensure that all operatives are conversant with the foregoing legislation and other relevant Codes of Practice and British Standards. The Contractor will make any notifications as are required under the terms of The Food and Environment Protection Act (1985), and will be responsible for any damage caused through the inappropriate use or application of any such hazardous substances.
- 1.16 Horticultural peat is not to be used as mulch on any beds or as a soil conditioner.
- 1.17 Where appropriate arisings from the site should be recycled. In the case of fallen or lopped tree material this can be located within areas of undergrowth, away from key public spaces, to form eco-stacks. The creation of such features must be done so in consultation with the Management Entity and should not be used as a measure to dump arisings on the site.
- 1.18 All arisings (unless otherwise specified) will be removed from site and deposited at an approved tip or registered green compost facility.
- 1.19 Watering operations will be carried out as specified in this management plan. A water source will be identified by the Management Entity. If no water source is available then watering will be carried out using a bowser.

Landscape Management Preambles

- 1.20 The Contractor will visit the site and take note of all existing conditions including levels, condition of vegetation, soil conditions, and access. No claims that are based on a lack of understanding of the site or the nature of the work required to carry out the operations in this plan will be entertained.
- 1.21 At all times care will be taken to avoid interference with the established levels and contours of the ground, and to avoid damage to footpaths, roads, drains, manholes and existing structures and vegetation. Damage so occasioned is to be made good at the Contractors expense.
- 1.22 All work will be carried out by experienced and qualified operatives holding the necessary training certificates to undertake the prescribed works. All works detailed in the following specifications shall be carried out in accordance with good horticultural practice, using materials, plant and machinery appropriate to the task, undertaken in such a manner that



avoids damage and/or nuisance to the site and its surroundings. Any plant material that dies as a result of the Contractors neglect will be replaced at their cost.

Litter Removal

- 1.23 The Contractor will ensure that the entire site is kept free of litter and other debris through a regular programme of monitoring, collection and disposal, coinciding with visits to maintain grassed areas and planting. All bins, including both litter and dog waste, will be emptied at each maintenance visit.
- 1.24 Particular care will be taken to remove all broken bottles, glass, tins, sharp objects and other items likely to constitute a hazard to the public.
- 1.25 The Contractor will take particular care when carrying out litter collection to ensure that any discarded needles or syringes are removed as soon as they are discovered. Such items must be packaged separately from other litter, and be contained within appropriately labelled, puncture-proof sharps containers and disposed of in a safe manner.
- 1.26 The Contractor must ensure that all operatives likely to come into contact with needles and syringes have been instructed in the means of safe collection and disposal, and that they have been issued with, and wear, adequate protective gloves and footwear to protect against penetration of needles and other sharp objects.
- 1.27 All litter and debris shall be removed off site to an authorised tip specified by the Contractor.
- 1.28 This shall be carried out in accordance with the Code of Practice on Litter and Refuse issued under Section 89 of the Environment Protection Act (1990).

SUDS Facility

- 1.29 The grass areas within the facility have been specified to cater for seasonal flooding and damp conditions, and will only require limited management as per details in the LEMP and/or HMMP.
- 1.30 The attenuation pond will be managed in accordance with CIRIA SUDs Manual C753. At each maintenance visit the Contractor will inspect the SUDS facility and remove any branches and leaf debris and/or any other object that are likely to restrict water



flow/capacity. All areas will be inspected and cleared of litter and other debris in accordance with the details set out above.

- 1.31 The Contractor will inspect all outfall features, check grilles (if present), and remove any obstructions.
- 1.32 Excess silt is to be removed from the base of facilities to maintain volume capacity and safeguard functionality of the balancing ponds themselves as necessary. A suggested 5-10 year clean-out cycle is to be adopted initially but this is to be monitored and reviewed by the contractor.
- 1.33 Where material is removed it should be placed for a 2 week period at the edge of the pond to allow insects and creature to return to the waterbody. Following this period all material will be removed from site to the Contractor's tip.
- 1.34 The management of the pond should be reviewed by the ecological consultant and in conjunction with the LEMP and/or HMMP to enhance biodiversity and wildlife potential where appropriate, and without affecting the drainage function of the pond.

Hard Surfaces and Street Furniture

- 1.35 The Contractor will check at each visit that all the hard surfaces and street furniture is safe and fit for purpose.
- 1.36 Hard surfaces are to be reviewed at each visit. Any damage is to be recorded and made good either during the visit or at the following visit. If the repairs cannot be carried out or completed the Contractor will make the area safe and/or cordon off any sections that present a hazard. Any such areas will be made good as soon as practically possible. Every effort should be made to match into the original materials, making sure line/levels are correctly adhered to.
- 1.37 All roads and paths will be treated with a suitable herbicide spray in accordance with Manufacturer's recommendations to remove weeds and moss. Hard surfaces will be swept at each visit.
- 1.38 All furniture will be maintained to a standard so that it is clean, safe and fit for purpose at all times. Any damage will be made good during the maintenance visit. Otherwise the item will be made safe and/or cordoned off and made good as soon a practically possible. All repairs to street furniture will be carried out using parts sourced from the supplying manufacturer and carried out in accordance with their guidelines.



Children's Play Area

- 1.1 Prior to the play area opening for public use the Management Entity will produce a play area risk assessment in accordance with the Management of Health and Safety at Work Regulations 1999 and RoSPA guidelines. This will include the identification of 'risk', assessing the risk and actions for risk reduction. This will be retained by the Management Entity and reviewed on an annual basis.
- 1.2 At each maintenance visit all areas will be cleared of litter and debris in accordance with the section set out above.
- 1.3 Dog fouling presents a significant health and safety risk within play areas. Play areas shall be inspected at every maintenance visit (no less frequently than weekly) and any issues with dog fouling addressed immediately. All play areas are to be maintained as dog free zones to prevent fouling and risk of dog attacks. The Management Entity shall take appropriate action to enforce this measure at all times.
- 1.4 All areas for play will be inspected and maintained in accordance with requirements of BS EN 1176/77 and best practice guidelines from the Royal Society for the Presentation of Accidents (ROSPA).
- 1.5 Recorded weekly safety inspections will be carried out by RoSPA qualified play inspectors, followed up by a 6 weekly structural check. The frequency may vary depending on use or with any variation agreed with the Management Entity and Local Authority following best practice guidance.
- 1.6 A visual assessment of all facilities will be undertaken at each site visit by the Management Entity. Any defects or hazards considered dangerous are to be dealt with immediately by immobilising the item and making the item safe until repair and only if necessary, will the play facilities will be closed until appropriate measures have been taken to make the facilities safe and fit for purpose. The Local Authority is to be notified of any closures
- 1.7 All inspections as set out above are to be carried out by a suitably qualified person (please refer to the Register of Play Inspectors International (RPII) for requirements).
- 1.8 An Outdoor Annual Inspector accredited by the RPII shall carry out certified inspections annually, and permanent record maintained to ensure continued compliance with legislation.
- 1.9 Contact details for the Management Entity will be displayed in a suitable location at each play facility and updated should this change promptly. The contact information must



include a direct telephone number so that any faults can be reported and dealt with in an appropriate timeframe. The Management Entity to have out of hours arrangements to allow reporting of faults at any time.

- 1.10 Maintenance of equipment and safety surfacing will be undertaken in strict accordance with the manufacturer's recommendations. This will include painting, vandalism, graffiti and sweeping.
- 1.11 All replacement parts must be sourced from an accredited manufacturer/supplier and be appropriate for the intended use. The Management Entity is to retain a record of all warranty inspections, maintenance, repairs and modifications carried out to any part of the play apparatus and/or associated safety surfacing.



2 MANAGEMENT SCHEME REVIEW & MAINTENANCE SCHEDULES

2.1 The sequence of agreement, monitoring and review is set out below. It is envisaged that at each stage agreement will be reached between the Contractor, Management Entity, and the Local Authority. It is the responsibility of the Contractor to bring to the attention of the Management Entity any issues that require immediate attention. Any such issues left unchecked that result in permanent damage or degradation of the landscape and associated environment will be put right at the Contractors expense. The stages of agreement, monitoring and review are set out below:

- Management scheme and annual maintenance schedules to be agreed by all parties involved (including the Local Authority) in the on-going management of the landscape and features specific to this plan;
- At the end of year 1 the Contractor, Management Entity and the Local Authority are to meet on site and review all open spaces;
- Following this monitoring stage appropriate adjustments to the management objectives, operations and frequencies of visits are to be agreed in writing between the Contractor, Management Entity, and the Local Authority;
- Monitoring visits and amendments to the plan are to be continuous between years 1 to years 5;
- At the end of year 5 there will be a wholesale review of this scheme and any changes to it (including the removal/insertion of operations and/or the change in frequency of operations) will be agreed between the Contractor, Management Entity, and the Local Authority.

2.2 The following tables set out the Year 1 maintenance schedule.



Management Scope: Maintenance Activity	Jan	Feb	Mar	April	May	June	July	Aug	Sept	Oct	Nov	Dec
Litter & debris removal												
Pick all litter from areas of hard and soft landscape and remove from site.	•	•	•	•	•	•	•	•	•	•	•	•
SUD's Facility												
Inspect SUDS facility and remove all litter and debris. Ensure that channel and outfalls are free of obstructions.	•	•	•	•	•	•	•	•	•	•	•	•
Programme specific operation to remove leaf litter during autumn months. Allow for 2 week creep back period.	•	•								•	•	•
Annual inspection to review management in conjunction with the LEMP and/or HMMP.										•		
Hard landscape & site furniture												
Inspect, clean, repair or replace.	•	•	•	•	•	•	•	•	•	•	•	•
Where repairs cannot be made good at time of visit and additional visit will be programmed as soon as practically possible to make any repair good and the item fit for purpose. During any such delay it is the Contractor's responsibility to ensure that all areas are made safe and remain safe until any such repairs are completed.	•	•	•	•	•	•	•	•	•	•	•	•
Children's Play Area												
Visually inspect children's play areas. Inspection to be carried out by qualified staff member. Observe any hazards, defect or act of vandalism.	•	•	•	•	•	•	•	•	•	•	•	•
20-24no. recorded inspection of the children's play areas. Inspection to be carried out by qualified staff member.	•	•	•	•	•	•	•	•	•	•	•	•



Initially frequency of play area maintenance to be every visit. To be reviewed / determined more accurately once in use and usage pattern can be confirmed. Best practice to be followed with any variation to monthly inspections will be agreed with the appointing authority.


Any repairs are to be carried out during the inspection. Otherwise the facility is to be made safe and works programmed within a reasonable timeframe.

Any repair works that cannot be carried out at the maintenance visit are to be programmed in as soon as practically possible taking into consideration order lead in times etc. Any temporary closure of and/or partial closure of the facility is to be checked on a daily basis to ensure that the area remain safe and for purpose until such time that the facility is in full working order.



APPENDIX A

Phase 1 On-plot Landscape Proposals - GL2024 LP 10-12 Rev E &
GL2024 LP 13-14 Rev D &;
Phase 1 POS Landscape Proposals – GL2024 LP 15-18 Rev B & 19 Rev A



Key

- Application boundary
- Timber bollards
- Footpath
- Footpath (transitional)
- Sealing
- Ullter bin
- Dog bin
- Play on the Way
- POW2 - Japanese Steps
- POW3 - Log Trail
- All play equipment and layout proposals to be specified in accordance with the requirements set out under the European Play Safety Standard EN1176 and the Disability Discrimination Act.
- Reinforced grass safety surfacing
- Gravel margins
- Hedgehog highways

Plant Schedule

Trees - On Plot

Abbr	Species	Supply	Size	Girth	Number
AMEBA	Amelanchier 'Ballerina'	PLT: Extra Heavy Standard: Clear Stem 175-200: 8R	425-600cm	14-16cm	4
AMARH	Amelanchier arborea 'Robin Hill'	PLT: Extra Heavy Standard: Clear Stem 175-200: 8R	425-600cm	14-16cm	1
BETJACA	Betula utilis jacquemontii	PLT: Extra Heavy Standard: Clear Stem 175-200: 8R	425-600cm	14-16cm	6
MAGKOIS	Magnolia kobus 'tsi'	PLT: Extra Heavy Standard: Clear Stem 175-200: 8R	425-600cm	14-16cm	7
SORARIA	Sorbus aria 'Magnifica'	PLT: Extra Heavy Standard: Clear Stem 175-200: 8R	425-600cm	14-16cm	1
PRUMAA	Prunus 'Amanogawa'	PLT: Extra Heavy Standard: Clear Stem 175-200: 8R	425-600cm	14-16cm	4

Trees - Street Trees

Abbr	Species	Supply	Size	Girth	Number
MALTRI	Malus 'Robusta'	STR: Semi Mature: Clear Stem 175-200: 8R	600cm	20-25cm	5
PRUPANA	Prunus 'Pandora'	STR: Semi Mature: Clear Stem 175-200: 8R	600cm	20-25cm	4

Trees - POS

Abbr	Species	Supply	Size	Girth	Number
ACECAMA	Acer campestre	POS: Selected Standard: Clear Stem 175-200: 8R	300-350cm	10-12cm	6
BEFE	Betula pendula	POS: Selected Standard: Clear Stem 175-200: 8R	300-350cm	10-12cm	10
CARBET	Carpinus betulus	POS: Selected Standard: Clear Stem 175-200: 8R	300-350cm	10-12cm	4
MALHU	Malus hupehensis	POS: Selected Standard: Clear Stem 175-200: 8R	300-350cm	10-12cm	2
MALSY	Malus sylvestris	POS: Selected Standard: Clear Stem 175-200: 8R	300-350cm	10-12cm	4
SORARIA	Sorbus aria	POS: Selected Standard: Clear Stem 175-200: 8R	300-350cm	10-12cm	14
SORARIA	Sorbus aucuparia	POS: Selected Standard: Clear Stem 175-200: 8R	300-350cm	10-12cm	8
TILCORRA	Tilia cordata	POS: Selected Standard: Clear Stem 175-200: 8R	300-350cm	10-12cm	3

Specimen Shrubs

Abbr	Species	Pot Size	Height	Habit	Density	Number
PHODA	Phormium 'Dazzler'	25L	100-125cm	Triple Crown		2
PHOJE	Phormium 'Jester'	25L	100-125cm	Triple Crown		7
PHOWAVA	Phormium 'Yellow Wave'	25L	100-125cm	Triple Crown		11
PHOFFR	Phloxia x fraseri 'Red Robin'	70-90L	225-250cm	Standard: 12-14cm gth		8
TRAJA	Trachospermum jasminoides	15L	100-150cm	Several Shoots: 3/5 brks		2

Single Species Hedgerows

Abbr	Species	Pot Size	Height	Habit	Density	Number
CARBET	Carpinus betulus	5L	60-80cm	Bushy	0.4Cfr	115
ELAEBC	Elaeagnus x ebbingei 'Compacta'	10L	80-100cm	Bushy	0.4Cfr	492
ELAEVL	Elaeagnus ebbingei 'Vivage'	10L	80-100cm	Bushy	0.5Cfr	524
EUJAPJH	Euonymus japonicus 'Jean Hugues'	10L	80-100cm	Bushy	0.3Cfr	382
GRUL	Griselinia littoralis	10L	80-100cm	Bushy	0.3Cfr	407

Native Mix Species Hedgerow

Abbr	Species	Supply	Height	Density	Mix %	Number
CORAV	Cornus ovellana	1+1: 3 brks: 8R	60-80cm	0.4Cfr Double Staggered at 0.4m offset	25%	287
CRAMON	Crataegus monogyna	1+1: 3 brks: 8R	60-80cm	0.4Cfr Double Staggered at 0.4m offset	50%	570
CORSA	Cornus sanguinea	3 brks: 8R	60-80cm	0.4Cfr Double Staggered at 0.4m offset	5%	59
ILEAQ	Ilex aquifolium	Bushy: 3L	60-80cm	0.4Cfr Double Staggered at 0.4m offset	5%	59
VIBOP	Viburnum opulus	1+1: 3 brks: 8R	60-80cm	0.4Cfr Double Staggered at 0.4m offset	10%	115
LOPNE	Lonicera periclymenum	Branches: 3L	60-80cm	0.4Cfr Double Staggered at 0.4m offset	2%	26
ROSCA	Rosa canina	1+1: 3 brks: 8R	60-80cm	0.4Cfr Double Staggered at 0.4m offset	3%	37

Shrubs - On Plot

Abbr	Species	Pot Size	Height	Habit	Density	Number
BRASU	Brodiaeopsis 'Sunshine'	10L	40-60cm	Bushy	0.7Cfr	94
CEATHR	Ceanothus thyrsiflorus repens	10L	40-60cm	Bushy	0.7Cfr	75
CHOAP	Choiysa 'Aztec Pearl'	10L	40-60cm	Bushy	0.7Cfr	158
CHOTES	Choiysa ternata 'Sundance'	10L	40-60cm	Bushy	0.7Cfr	269
EUFOENG	Euonymus fortunei 'Emerald 'n' Gold'	10L	30-40cm	Bushy	0.7Cfr	112
EUFOENG	Euonymus fortunei 'Emerald Gaiety'	10L	30-40cm	Bushy	0.7Cfr	233
HEBMA	Hebe 'Majorie'	10L	40-60cm	Bushy	0.7Cfr	73
HEBMW	Hebe 'Mrs Winder'	10L	40-60cm	Bushy	0.7Cfr	52
HEBPQ	Hebe 'Purple Queen'	10L	40-60cm	Bushy	0.7Cfr	280
HEBALRE	Hebe abicans 'Red Edge'	10L	30-40cm	Bushy	0.7Cfr	50
HEBRS	Hebe pinguifolia 'Sutherland'	10L	30-40cm	Bushy	0.7Cfr	90
HYPHI	Hypericum 'Hidcote'	10L	40-60cm	Bushy	0.7Cfr	69
LAVANHII	Lavandula angustifolia 'Hidcote'	10L	30-40cm	Bushy	0.7Cfr	94
LAVANMU	Lavandula angustifolia 'Munstead'	10L	30-40cm	Bushy	0.7Cfr	50
PITTEG	Pittosporum tenuifolium 'Golf Ball'	10L	30-40cm	Bushy	0.7Cfr	66
PITTEG	Pittosporum tenuifolium 'Tom Thumb'	10L	30-40cm	Bushy	0.7Cfr	89
PRULIAC	Prunus laurocerasus 'Otto Luyken'	10L	60-80cm	Bushy	0.7Cfr	133
ROSF	Rosmarinus officinalis	10L	40-60cm	Bushy	0.7Cfr	57
SARHOHU	Sarcococca humilis	10L	30-40cm	Bushy	0.7Cfr	28
SKIJARU	Skimmia japonica 'Rubella'	10L	40-60cm	Bushy	0.7Cfr	99
VIBDA	Viburnum davidii	10L	40-60cm	Bushy	0.7Cfr	59

Shrubs Screen Mix

Abbr	Species	Pot Size	Height	Habit	Density	Number
AUCJACR	Aucuba japonica 'Crotanifolia'	10L	60-80cm	Bushy	0.75Cfr	85
CORALE	Cornus alba 'Elegantissima'	3L	60-80cm	Branches	0.75Cfr	18
ELAPUNA	Elaeagnus pungens 'Maculata'	10L	80-100cm	Bushy	0.75Cfr	18
FATJA	Fatsia japonica	10L	80-100cm	Bushy	0.75Cfr	86
PHOFFR	Phloxia x fraseri 'Red Robin'	10L	80-100cm	Bushy	0.75Cfr	85

Drawing to be read in conjunction with GL2024 SP 01 Landscape Specification.



Play on the way

Scale Bar

0m 5m 10m 15m 20m 25m

Registered Practice

tel: 01530 265688 | email: info@golbyandluck.co.uk | web: www.golbyandluck.co.uk

This drawing has been produced by GOLBY AND LUCK LTD & is copyright reserved. All rights reserved. No part of this drawing may be reproduced without the written permission of GOLBY AND LUCK LTD.

Shrubs - Ornamental's in POS Areas						
Abbr	Species	Pot Size	Height	Habit	Density	Number
CAROSE	Carex oshimensis 'Evergold'	3L			0.6Cfr	9
CHOSUNA	Choiysa ternata 'Sundance'	3L	20-30cm	Bushy	0.6Cfr	9
DESCCE	Deschampsia cespitosa	3L		Full Pot	0.6Cfr	11
LAVANHII	Lavandula angustifolia 'Hidcote'	3L	20-30cm	Bushy	0.6Cfr	10
LIRMU	Liriodendron muscari	3L		Full Pot	0.6Cfr	10
MISSIML	Miscanthus sinensis 'Morning Light'	3L		Full Pot	0.6Cfr	11
PENVI	Pennisetum villosum	3L		Full Pot	0.6Cfr	13
ROOF	Rosmarinus officinalis	3L	20-30cm	Bushy	0.6Cfr	6
						Total :79

Shrubs - Highway Verge						
Abbr	Species	Pot Size	Height	Habit	Density	Number
LIRMU	Liriodendron muscari	3L		Full Pot	0.5Cfr	115
LIRMU	Liriodendron muscari	3L		Full Pot	0.5Cfr	51
PACTEGC	Pachysandra terminalis 'Green Carpet'	3L	10-20cm	Bushy	0.5Cfr	112
RUDRUG	Rudbeckia fulgida sylvatica 'Goldsturm'	3L		Full Pot	0.5Cfr	100
CAROSE	Carex oshimensis 'Evergold'	3L	20-30cm	Bushy	0.6Cfr	48
HEUMIPP	Heuchera micrantha 'Palace Purple'	5L		Full Pot	0.6Cfr	88
						Total :514

Rain Gardens						
Abbr	Species	Pot Size	Height	Habit	Density	Number
ASTWH	Astilbe White	3L		Full Pot	0.45Cfr	79
BISOFFS	Bistorta officinalis 'Superba'	3L		Full Pot	0.45Cfr	103
CARAC	Carex acuta	3L		Well Rooted	0.45Cfr	103
DECGU	Deschampsia cespitosa 'Goldstar'	2L		Full Pot	0.45Cfr	127
IRIPS	Iris pseudacorus	2L		Well Rooted	0.45Cfr	103
						Total :515

Turf Areas			
Seed Mix Name	Seed Mix Supplier	Density	
Meditation turf	Rotax Ltd		

Amenity Grassland Areas			
Seed Mix Name	Seed Mix Supplier	Density	
EL1 - Flowering Lawn Mix	Emmagine Seeds	4g/m ²	

Amenity Meadow Areas			
Seed Mix Name	Seed Mix Supplier	Density	
EM6 - Chalk & Limestone Soils	Emmagine Seeds	4g/m ²	

Retained Grassland (over seed were required)			
Seed Mix Name	Seed Mix Supplier	Density	
EH1 - Hedgerow Mix	Emmagine Seeds	4g/m ²	

Location Plan

Revision

Rev	Date	Notes
1	20/04/2025	Issued for the latest planning consent.
2	30/07/2025	Application locations and submission position updated.
3	26/10/2025	Tree species data revised.
4	19/02/2026	Updated to latest planning consent and JPA comments.
5	24/02/2026	Updated to latest planning consent.



Client
BDW North Thames

Scale
1:250 @ A0

Date
19/03/2025

GL2024 LP 10E

golby+luck
landscape architects



5

- 

Turf Areas
Seed Mix Name **Seed Mix Supplier**
 Medication Turf Rolawn Ltd
- 

Amenity Grassland Areas
Seed Mix Name **Seed Mix Supplier** **Density**
 BL1 - Flowering Lawn Mix Emorsgate Seeds 4g/m²
- 

Amenity Meadow Areas
Seed Mix Name **Seed Mix Supplier** **Density**
 BM6 - Chalk & Limestone Soils Emorsgate Seeds 4g/m²
- 

Related Grassland (over seed were required)
Seed Mix Name **Seed Mix Supplier** **Density**
 BH1 - Hedgerow Mix Emorsgate Seeds 4g/m²

Rev	Date	Notes	By	Chk
A	20/02/24	updated to the latest planning layout.	AL	AL
B	20/07/25	Application boundary and substation position updated.	AL	AL
C	26/10/25	Tree species are revised.	JS	AL
D	19/02/26	updated to latest planning layout and J16 comments.	AL	AL
E	26/02/26	updated to latest planning layout.	AL	AL

Highover Farm, Hitchin,
North Hertfordshire

Drawing title

On Plot Landscape Proposals
David Wilson Homes - ph1

(Sheet 2 of 3)

Status

PLANNING

Client

BDW North Thames

Scale

1:250 @ A0

Drawn By

AL

Checked By


HJ


Date


19/05/2025

Reference

GL2024 LP 11E





 tel: 01330 265688 | email: info@godyanduck.co.uk | web: www.godyanduck.co.uk
This drawing has been produced by GODY AND DUCK Ltd. All rights reserved. Outline Survey Licence No. AC00001616 registered with HM Land Registry 2012. © Crown Copyright. All Rights Reserved. 12/01/2016




Key

- Application boundary
- Footpath
2m wide bitumen macadam finish with precast concrete edging.
- Sealing
Litchard Seal (Ref: BX17 4071/S) heavy duty galvanised steel framed seal with seven slots in sturdy timber and a double slatted backrest and armrests. As supplied by Broxap Ltd or similar approved. Installed on semi bound surface (haggin) as per the footpaths.
- Litter bin
Derby weyburn (Ref: BX 2550-WB) steel litter bin as supplied by Broxap or similar approved.
- Dog bin
Sirius Dog Waste Bin (Ref: BX45G 2591-FW) galvanised steel bin with a top-opening lid as supplied by Broxap or similar approved.
- Play on the Way
POW2 - Japanese Steps (Ref: J4904). Supplied by Pruldic: Play Ltd or similar approved.
- POW5 - Climbing Logs (Ref: J4905). Supplied by Pruldic: Play Ltd or similar approved.
- All play equipment and layout proposals to be specified in accordance with the requirements set out under the European Play Safety Standard EN1176 and the Equality Discrimination Act.
- Reinforced grass safety surfacing
Play manufacturers to detail in accordance with EN 1176.
- Gravel margins
Loose gravel to be laid over weed suppressing membrane where no planting is possible due to restricted space.
- Hedgehog highways
Gap/holes built into the bottom of a garden fence, wall or hedge, which enables hedgehogs to easily move between gardens. Additional ecological enhancements are detailed within the Landscape and Ecological Management and Enhancements document, which forms part of the site wide OLEMP.

Plant Schedule

Trees - On Plot						
Abbr	Species	Supply	Size	Grith	Number	
AMARH	Amelanchier arborea 'Robin Hill'	PLT: Heavy Standard :Clear Stem 175-200 :BR	350-425cm	12-14cm	2	
MAGKOIS	Magnolia kobus 'Isis'	PLT: Heavy Standard :Clear Stem 175-200 :BR	350-425cm	12-14cm	8	
SORAM	Sorbus aria 'Magnifica'	PLT: Heavy Standard :Clear Stem 175-200 :BR	350-425cm	12-14cm	2	
BETJAC	Betula utilis 'jacquemontii'	PLT: Extra Heavy Standard :Clear Stem 175-200 :C: SOL	425-600cm	14-16cm	9	
SORAUSTR	Sorbus aucuparia 'Streetwise'	PLT: Extra Heavy Standard :Clear Stem 175-200 :BR	425-600cm	16-18cm	5	
PRUAMAA	Prunus 'Amanogawa'	PLT: Extra Heavy Standard :Clear Stem 175-200 :BR	425-600cm	16-18cm	3	
Total: 29						
Trees - Street Trees						
Abbr	Species	Supply	Size	Grith	Number	
MALTRI	Malus tibibata	STR: Semi Mature :Clear Stem 175-200 :RB	600cm+	20-25cm	4	
PRUPANA	Prunus 'Pandora'	STR: Semi Mature :Clear Stem 175-200 :RB	600cm+	20-25cm	1	
Total: 5						
Trees - POS						
Abbr	Species	Supply	Size	Grith	Number	
PRUPELA	Prunus vulum 'Plena'	POS: Selected Standard :Clear Stem 175-200 :BR	300-350cm	10-12cm	3	
SORLUTA	Sorbus aria 'Lutescens'	POS: Selected Standard :Clear Stem 175-200 :BR	300-350cm	10-12cm	1	
ACEFRAB	Acer x freemantli 'Autumn Blaze'	POS: Extra Selected Standard :Clear Stem 175-200 :RB	300-350cm	18-20cm	1	
Total: 5						
Specimen Shrubs						
Abbr	Species	Pot Size	Height	Habit	Density	Number
PHOJE	Phormium 'Jester'	25L	100-125cm	Triple Crown		7
PHOWAVA	Phormium 'Yellow Wave'	25L	100-125cm	Triple Crown		13
PHOPFR	Phoroxia x fraseri 'Red Robin'	70-90L	225-350cm	Standard	12-14cm gth	13
TRAJA	Trachelospermum jasminoides	15L	100-150cm	Several Shoots :3/5 brks	Framed 14	1
Total: 39						
Single Species Hedgerows						
Abbr	Species	Pot Size	Height	Habit	Density	Number
ELACOM	Elaeagnus x ebbingei 'Compacta'	10L	50-60cm	Bushy 0.4Ctr	133	1
ELAEBC	Elaeagnus x ebbingei 'Compacta'	10L	80-100cm	Bushy 0.4Ctr	604	1
ELAEVL	Elaeagnus ebbingei 'Vivaleg'	10L	80-100cm	Bushy 0.4Ctr	1240	1
OSMBU	Osmanthus burkwoodii	5L	40-60cm	Bushy 0.35Ctr	86	1
Total: 2063						
Shrubs - On Plot						
Abbr	Species	Pot Size	Height	Habit	Density	Number
BRASU	Brachyglottis 'Sunshine'	10L	40-60cm	Bushy 0.7Ctr	135	1
CEATHR	Ceanothus thyrsiflorus repens	10L	40-60cm	Bushy 0.7Ctr	251	1
CHOAP	Choiysia 'Aztec Pearl'	10L	40-60cm	Bushy 0.7Ctr	117	1
CHOIES	Choiysia ternata 'Sundance'	10L	40-60cm	Bushy 0.7Ctr	381	1
EUOFEOG	Euonymus fortunei 'Emerald 'n' Gold'	10L	30-40cm	Bushy 0.7Ctr	185	1
EUOFEOG	Euonymus fortunei 'Emerald Gaiety'	10L	30-40cm	Bushy 0.7Ctr	221	1
HEBMAR	Hebe 'Marjorie'	10L	30-40cm	Bushy 0.7Ctr	58	1
HEBMW	Hebe 'Mrs Winder'	10L	40-60cm	Bushy 0.7Ctr	112	1
HEBPQ	Hebe 'Purple Queen'	10L	40-60cm	Bushy 0.7Ctr	212	1
HEBALRE	Hebe abataensis 'Red Edge'	10L	30-40cm	Bushy 0.7Ctr	190	1
HEBPIS	Hebe pingulifolia 'Sutherlandii'	10L	30-40cm	Bushy 0.7Ctr	54	1
HYPHI	Hypericum 'Hidcote'	10L	40-60cm	Bushy 0.7Ctr	58	1
LAVANHII	Lavandula angustifolia 'Hidcote'	10L	30-40cm	Bushy 0.7Ctr	75	1
LAVANMU	Lavandula angustifolia 'Munstead'	10L	30-40cm	Bushy 0.7Ctr	45	1
PITTEGB	Pittosporum tenuifolium 'Golf Ball'	10L	30-40cm	Bushy 0.7Ctr	114	1
PITTEI	Pittosporum tenuifolium 'Tom Thumb'	10L	30-40cm	Bushy 0.7Ctr	69	1
PRULAOL	Prunus laurocerasus 'Otto Luyken'	10L	60-80cm	Bushy 0.7Ctr	60	1
ROSOF	Rosmarinus officinalis	10L	40-60cm	Bushy 0.7Ctr	64	1
SARJHU	Sarcococca humilis	10L	30-40cm	Bushy 0.7Ctr	62	1
SKJARIU	Skimmia japonica 'Rubella'	10L	40-60cm	Bushy 0.7Ctr	158	1
VIBDA	Viburnum davidii	10L	40-60cm	Bushy 0.7Ctr	14	1
Total: 2635						
Shrubs Screen Mix						
Abbr	Species	Pot Size	Height	Habit	Density	Number
AUCJACR	Aucuba japonica 'Crotanifolia'	10L	60-80cm	Bushy 0.75Ctr	100	1
CORALE	Cornus alba 'Elegantissima'	3L	60-80cm	Branched 0.75Ctr	46	1
ELAPUMA	Elaeagnus pungens 'Maculata'	10L	80-100cm	Bushy 0.75Ctr	46	1
FATJIA	Fatsia japonica	10L	80-100cm	Bushy 0.75Ctr	70	1
PHOPFR	Phoroxia x fraseri 'Red Robin'	10L	80-100cm	Bushy 0.75Ctr	100	1
Total: 362						
Rain Gardens						
Abbr	Species	Pot Size	Height	Habit	Density	Number
ASTWH	Astilbe White	3L	Full Pot	0.45Ctr	21	1
BISOFFS	Bistorta officinalis 'Superba'	3L	Full Pot	0.45Ctr	27	1
CARAC	Carex acutata	2L	Well Rooted	0.45Ctr	27	1
DECGU	Deschampsia cespitosa 'Goldtau'	3L	Full Pot	0.45Ctr	33	1
IRIPS	Iris pseudacorus	2L	Well Rooted	0.45Ctr	27	1
Total: 135						
Turf Areas						
Seed Mix Name	Seed Mix Supplier					
Medallion turf	Rotolun Ltd					


Drawing to be read in conjunction with GL2024 SP 01 Landscape Specification.



Key		Application boundary
TR2	Footpath	2m wide bitumen macadam finish with precast concrete edging.
	Sealing	Ulrichard Seal (Ref: BX17 4071/S) heavy duty galvanised steel framed seal with seven slots in sturdy timber and a double slatted bracket and armrests. As supplied by Broxap Ltd or similar approved. Installed on semi bound surface (hoggin) as per the manufacturer's instructions.
B	Litter bin	Derby weyburn (Ref: BX 2550-WBN) steel litter bin as supplied by Broxap or similar approved.
B	Dog bin	Sirus Dog Waste Bin (Ref: BX45G 2591-FW) galvanised steel bin with a top-opening lid as supplied by Broxap or similar approved.
POW	Play on the Way	POW2 - Japanese Steps (Ref: J4904). Supplied by Pruldic: Play Ltd or similar approved.
POW	POW5 - Climbing Logs	(Ref: J4905). Supplied by Pruldic: Play Ltd or similar approved.
	All play equipment and layout proposals to be specified in accordance with the requirements set out under the European Play Safety Standard EN1176 and the Disability Discrimination Act.	
	Reinforced grass safety surfacing	Play manufacturers to detail in accordance with EN 1176.
	Gravel margins	Loose gravel to be laid over weed suppressing membrane where no planting is possible due to restricted space.
	Hedgehog highways	Gap/holes built into the bottom of a garden fence, wall or hedge, which enables hedgehogs to easily move between gardens. Additional ecological enhancements are detailed within the Landscape and Ecological Management and Enhancements document, which form part of the site wide OLEMP.
Plant Schedule		
Abb	Species	Supply
AMARH	Amelanchier arborea 'Robin Hill'	PLT: Heavy Standard :Clear Stem 175-200 :BR
MAGKOS	Magnolia kobus 'Isis'	PLT: Heavy Standard :Clear Stem 175-200 :BR
SOKAM	Sorbus aria 'Magnifica'	PLT: Heavy Standard :Clear Stem 175-200 :BR
BETJACA	Betula utilis 'jacquemontii'	PLT: Extra Heavy Standard :Clear Stem 175-200 :C: SOL
SORAUCST	Sorbus aucuparia 'Streetwise'	PLT: Extra Heavy Standard :Clear Stem 175-200 :BR
PRUAMAA	Prunus 'Amanogawa'	PLT: Extra Heavy Standard :Clear Stem 175-200 :BR
Trees - Street Trees		
Abb	Species	Supply
MALTRI	Malus flabellata	STR: Semi Mature :Clear Stem 175-200 :RB 600cm+ 20-25cm 4
PRUPANA	Prunus 'Pandora'	STR: Semi Mature :Clear Stem 175-200 :RB 600cm+ 20-25cm 1
Trees - POS		
Abb	Species	Supply
PRUPLA	Prunus avium 'Plena'	POS: Selected Standard :Clear Stem 175-200 :BR
SORLUTA	Sorbus aria 'Lutescens'	POS: Selected Standard :Clear Stem 175-200 :BR
ACERFAB	Acer x freemianii 'Autumn Blaze'	POS: Extra Selected Standard :Clear Stem 175-200 :RB 300-350cm 18-20cm 1
Specimen Shrubs		
Abb	Species	Pot Size Height Habit Density Number
PHOJE	Phormium 'Jester'	25L 100-125cm Triple Crown 7
PHOWAVA	Phormium 'Yellow Wave'	25L 100-125cm Triple Crown 7
PHOPHR	Phorinia x traseri 'Red Robin'	70-90L 225-350cm Standard: 12-14cm gth 13
TRAJA	Trachelospermum jasminoides	15L 100-150cm Several Shoots :3/5 barks :Framed 14
Single Species Hedgerows		
Abb	Species	Pot Size Height Habit Density Number
ELACOM	Elaeagnus x ebbingei 'Compacta'	5L 60-80cm Bushy 0.5Ctr 133
ELAEB	Elaeagnus x ebbingei 'Compacta'	10L 80-100cm Bushy 0.4Ctr 604
ELAEV	Elaeagnus ebbingei 'Vivaleg'	10L 80-100cm Bushy 0.4Ctr 1240
OSMBU	Osmanthus burkwoodii	15L 40-60cm Bushy 0.35Ctr 86
Shrubs - On Plot		
Abb	Species	Pot Size Height Habit Density Number
BRASU	Brachyglottis 'Sunshine'	10L 40-60cm Bushy 0.7Ctr 135
CEATHR	Ceanothus thyrsiflorus repens	10L 40-60cm Bushy 0.7Ctr 251
CHOPAP	Chiosya 'Aztec Pearl'	10L 40-60cm Bushy 0.7Ctr 117
CHOTES	Chiosya temata 'Sundance'	10L 40-60cm Bushy 0.7Ctr 381
EUOFOENG	Euonymus fortunei 'Emerald n' Gold'	10L 30-40cm Bushy 0.7Ctr 185
Shrubs Screen Mix		
Abb	Species	Pot Size Height Habit Density Number
AUCJACR	Aucuba japonica 'Crotanifolia'	10L 60-80cm Bushy 0.75Ctr 100
CORALE	Cornus alba 'Elegantissima'	3L 60-80cm Branched 0.75Ctr 46
ELAPUMA	Elaeagnus pungens 'Maculata'	10L 80-100cm Bushy 0.75Ctr 46
FATJA	Fatsia japonica	10L 80-100cm Bushy 0.75Ctr 70
PHOPHR	Phorinia x traseri 'Red Robin'	10L 80-100cm Bushy 0.75Ctr 100



Play on the way



Key		Application boundary
	Timber bollards	To align the perimeters of the highways to defer adhoc parking, 200mm square timber bollards with chamfered top, 450mm high (above ground) and posts to be installed at no wider than 2m centres.
	Combined cycle/footpath	3.5m wide bitumen macadam finish with precast concrete edging.
	Footpath	2m wide semi bound surface (hoggin) with pre-cast concrete edging like Cedec/ Breedon or similar approved.
	Combined cycle/footpath	3.5m wide semi bound surface (hoggin) with pre-cast concrete edging like Cedec/ Breedon or similar approved.
	Footpath	2m wide unbound whin or granite dust path with fantailised timber edging or similar approved.
	Seating area (by play area)	Semi bound surface (hoggin) with pre-cast concrete edging like Cedec/ Breedon or similar approved with feature 100mm x 100mm silver grey Conservation X sets as supplied by Marshall or similar approved. Outer circle edge 3 course, inner circle edge 1 course as shown.
	Footpath (transitional zone)	2m depth of tarmac surfacing adjacent to highway edge to buffer reduce the milligation of footpath materials onto the highway.
	Mown paths	1m wide grass strips adjacent to hard surfaced areas (road/path) to be regularly cut (circa. 12 cuts a year) to improve presentation.
	Seating	Urchard Seat (Ref: BX17 4071/S) heavy duty galvanised steel framed seat with seven slats in sturdy timber and a double slatted backrest and armrest. As supplied by Broxap Ltd or similar approved. Installed on semi bound surface (hoggin) as per the footpaths.
	Seating	Estate Rustic 3 Star Seat (Ref: BX17 4022) As supplied by Broxap Ltd or similar approved. Installed beneath unbound whin or granite dust as per the footpaths.
	Litter bin	Derby weyburn (Ref: BX 2550-WBN) steel litter bin as supplied by Broxap or similar approved.
	Dog bin	Sinus Dog Waste Bin (Ref: BX45G 2591-PM) galvanised steel bin with a top-opening lid as supplied by Broxap or similar approved.
	Perimeter bunds/rounding	Earthmodelling that take place using the subsoil previously stored on site and laid in 300mm layers at a time, and consolidated as work proceeds. Prior to top soil spreading (only for planting areas), the subsoil surface shall be loosened using a single line ripper to a depth of 450mm at 1.0m centres. Topsoil shall be spread evenly over the formation levels in layers not exceeding 150mm to a depth of 450mm to the areas to be planted up. Areas to be grass seeded, cultivated subsoil to be used. All slopes shall be graded with a rigid blade grader and consolidated to proposed levels. The gradient of the slopes shall be smooth-flowing, no steeper than 1:3 and marring with all existing levels.

For ecology enhancements please refer to the Landscape and Ecological Management and Enhancements document, which forms part of the site wide QLEMP.

KEY - LEAP & Natural Play	
	Seating
	Picnic table
	Fenced play - Secure play
	Gate access to secure play
	Maintenance gate
	Play signage
	Reinforced grass safety surfacing
	Bonded rubber mulch safety surfacing
	Post and wire fence


PLAY AREA SCHEDULE	
1. J49147 Market (INC)	
2. J2404/ Wok (INC)	
3. J4918 Double cradle seat.	
4. J4910 Double flat seat.	
5. J4938 Multi-play unit.	
Exploratory play items outside the secure play area	
6. J3426 Pixel panel (INC)	
7. 3 him trial units: J4904 (Japanese steps), J4902 (net walkway), J4903 (balance beam)	
8. 2 him trail units: J4901 (log walkway), J4904 (Goleway)	
9. Tree trunks, designed and hand-built, bark removed and sanded to provide a splinter and snag-free play surface. Supplied by Copper Beech Play or similar approved.	
10. Play/look out grass mound. Construction as per earth mounding specification. Maximum height of 1.6m. Gradient no steeper than 1:3.	
INC - Inclusive play equipment is designed to be accessible and enjoyable for all children, regardless of their abilities, including those with physical, sensory, or cognitive needs.	
All play equipment as supplied by ProLudic Ltd [www.proludic.co.uk] or similar product from an approved manufacturer. All wooden/robino post in contact with the ground to be filled with metal feet to extend life expectancy of apparatus. All play equipment and layout proposals to be specified in accordance with the requirements set out under BS EN 1176 and Equality Act 2010. Following the agreement of play equipment and the general arrangement the selected manufacturer's details will be submitted to the local council for approval along with the finalised proposals and accompanying 7x1500mm A3 print.	



Plant Schedule						
Trees - Feature				Size	Girth	Number
Abbr	Species	Supply				
FAGPURA	Fagus sylvatica 'Purpurea'	FTE Heavy Standard :Clear Stem 175-200 :R8		350-425cm	12-14cm	3
LIQSTAMBR	Liquidambar styraciflua	FTE Semi mature :Clear Stem min. 200:R8		600cm+	20-25cm	1
PYRCHAC	Pyrus calleryana 'Chariticeae'	FTE Semi Mature :Clear Stem 175-200 :R8		600cm+	25-30cm	7
						Total :11
Trees - POS						
Abbr	Species	Supply		Size	Girth	Number
BETPENA	Betula pendula	POS :Multi-Stemmed :3/5 brks :C 30L		250-300cm		9
ALINGLIA	Alnus glutinosa	POS :Standard :Clear Stem 150-175 :C 30L		250-300cm	8-10cm	13
BETNIGA	Betula nigra	POS :Standard :Clear Stem 150-175 :C 30L		250-300cm	8-10cm	9
QUEROBA	Quercus robur	POS :Standard :Clear Stem 150-175 :C 30L		250-300cm	8-10cm	10
SALALBA	Salix alba	POS :Standard :Clear Stem 150-175 :C 30L		250-300cm	8-10cm	12
SAIFR	Salix fragilis	POS :Standard :Clear Stem 150-175 :C 30L		250-300cm	8-10cm	6
ACECAMA	Acer campestre	POS :Selected Standard :Clear Stem 175-200 :R8		300-350cm	10-12cm	21
CARBET	Carpinus betulus	POS :Selected Standard :Clear Stem 175-200 :R8		300-350cm	10-12cm	2
PRUPLEA	Prunus avium 'Pleno'	POS :Selected Standard :Clear Stem 175-200 :R8		300-350cm	10-12cm	20
SORARIA	Sorbus aria	POS :Selected Standard :Clear Stem 175-200 :R8		300-350cm	10-12cm	16
SORTO	Sorbus torminalis	POS :Selected Standard :Clear Stem 175-200 :R8		300-350cm	10-12cm	6
						Total :118
Specimen Shrubs						
Abbr	Species	Pot Size	Height	Habit	Number	
FATJAPA	Fatsia japonica	20L	150-175cm	Bushy	1	
PHOWAYA	Phormium 'Yellow Wave'	23L	100-125cm	Triple Crown	3	
						Total :4
Single Species Hedgerows						
Abbr	Species	Pot Size	Height	Habit	Density	Number
ELAEBE	Elaeagnus x ebbingei 'Compacta'	10L	80-100cm	Bushy	0.4Cfr	230
EUJAPH	Euonymus japonicus 'Jean Hughes'	3L	60-80cm	Bushy	0.25Cfr	91
INSTANT	Native Mix Species Instant Hedge	INSTANT HEDGE 125-150cm	Bushy	through 1Cfr		18
PHOFRR	Photinia x fraseri 'Red Robin'	INSTANT HEDGE 125-150cm	Bushy	through 1Cfr		47
						Total :386
Native Mix Species Hedgerow						
Abbr	Species	Supply	Height	Density		Mix % Number
CORAV	Cornus avellana	1+1 :3 brks :R8	60-80cm	0.4Cfr Double Staggered at 0.4m offset	25%	9
CRAMON	Crataegus monogyna	1+1 :3 brks :R8	60-80cm	0.4Cfr Double Staggered at 0.4m offset	50%	18
CORSA	Cornus sanguinea	3 brks :C	60-80cm	0.4Cfr Double Staggered at 0.4m offset	5%	2
ILEAQ	Ilex aquifolium	Bushy :3L	40-60cm	0.4Cfr Double Staggered at 0.4m offset	5%	2
VIBOP	Viburnum opulus	1+1 :3 brks :R8	60-80cm	0.4Cfr Double Staggered at 0.4m offset	10%	4
LOHPE	Lonicera periclymenum	Branched :Caned :3L	60-80cm	0.4Cfr Double Staggered at 0.4m offset	2%	1
ROSCA	Rosa canina	1+1 :3 brks :R8	60-80cm	0.4Cfr Double Staggered at 0.4m offset	3%	2
						Total :38
Native Mix Species Hedgerow (Thornless)						
Abbr	Species	Pot Size	Height	Density		Mix % Number
CORSA	Cornus sanguinea	1+1 :3 brks :R8	60-80cm	0.3Cfr Double Staggered at 0.3m offset	10%	47
CORAV	Cornus avellana	1+1 :3 brks :R8	60-80cm	0.3Cfr Double Staggered at 0.3m offset	25%	117
LIGUVI	Ligustrum vulgare	Bushy :C 2L	60-80cm	0.3Cfr Double Staggered at 0.3m offset	25%	117
ACCA	Acer campestre	1+1 :3 brks :R8	60-80cm	0.3Cfr Double Staggered at 0.3m offset	30%	139
VIBOP	Viburnum opulus	1+1 :3 brks :R8	60-80cm	0.3Cfr Double Staggered at 0.3m offset	10%	47
						Total :467
Shrubs - Site Entrance						
Abbr	Species	Pot Size	Height	Habit	Density	Number
CAREVI	Carex oshimensis 'Everest'	5L	Full Pot	0.5Cfr	42	
HEUMIPP	Heuchera micrantha 'Palace Purple'	5L	Full Pot	0.5Cfr	13	
HEBPS	Hebe pinguifolia 'Sutherlandii'	10L	30-40cm	Bushy	0.6Cfr	54
MISSKLF	Miscanthus sinensis 'Klein Fontaine'	5L	Full Pot	0.6Cfr	32	
PHOPLBL	Phormium 'Platt's Black'	10L	60-80cm	Triple crown	0.7Cfr	38
						Total :179
Shrubs - Ornamentals in POS/Play Area						
Abbr	Species	Pot Size	Height	Habit	Density	Number
CAROSE	Cornus oshimensis 'Evergold'	3L	20-30cm	Bushy	0.6Cfr	25
LAVANNH	Lavandula angustifolia 'Hidcote'	3L	Full Pot	0.6Cfr	25	
LIROPE	Liriodendron muscari	3L	Full Pot	0.6Cfr	25	
PENVI	Pennisetum vilosum	3L	Full Pot	0.6Cfr	29	
						Total :99
Herbaceous Grasses						
Abbr	Species	Pot Size	Height	Habit	Density	Number
DESCA	Deschampsia caespitosa	3L	Full Pot	0.5Cfr	331	
DECGU	Deschampsia caespitosa 'Goldtau'	3L	Full Pot	0.5Cfr	511	
LUZNIWA	Luzula nivea	3L	Full Pot	0.5Cfr	249	
MISSIML	Miscanthus sinensis 'Morning Light'	3L	Full Pot	0.5Cfr	485	
						Total :1576
Native Structural Planting Mix						
Abbr	Species	Supply	Height	Mix	Density	Area Number
ACCA	Acer campestre	1+2 :Whip :5 brks :R8	125-150cm	5%	1Cfr	505.09m²
ALINGL	Alnus glutinosa	1+2 :Whip :3 brks :R8	125-150cm	3%	1Cfr	303.06m²
BETPENA	Betula pendula	1+2 :Whip :3 brks :R8	125-150cm	2%	1Cfr	202.04m²
CARBETA	Carpinus betulus	1+2 :Whip :4 brks :R8	125-150cm	5%	1Cfr	505.09m²
CORSA	Cornus sanguinea	1+1 :3 brks :R8	60-80cm	10%	1Cfr	101.10m²
CORAVEA	Cornus avellana	1+1 :3 brks :R8	60-80cm	15%	1Cfr	151.29m²
CRMON	Crataegus monogyna	1+1 :3 brks :R8	60-80cm	35%	1Cfr	355.69m²
LOHFER	Lonicera periclymenum	Bushy :C 2L	60-80cm	2%	1Cfr	202.04m²
MASY	Malus sylvestris	1+2 :Whip :4 brks :R8	125-150cm	3%	1Cfr	303.06m²
PRAV	Prunus avium	1+2 :Whip :3 brks :R8	125-150cm	2%	1Cfr	202.04m²
PRUSPIB	Prunus spinosa	1+1 :3 brks :R8	60-80cm	5%	1Cfr	505.09m²
QURO	Quercus robur	1+2 :Whip :4 brks :R8	125-150cm	5%	1Cfr	505.09m²
ROSCA	Rosa canina	1+1 :3 brks :R8	60-80cm	3%	1Cfr	303.06m²
VIBOPUA	Viburnum opulus	1+1 :3 brks :R8	60-80cm	5%	1Cfr	505.09m²
						Total :10101.93m² Total :10114
Native Scrub Planting Mix						
Abbr	Species	Supply	Height	Mix	Density	Area Number
CORSA	Cornus sanguinea	1+1 :3 brks :R8	60-80cm	15%	1Cfr	323.4m²
CORAV	Cornus avellana	1+1 :3 brks :R8	60-80cm	25%	1Cfr	559.01m²
CYTSC	Cytisus scoparius	1+1 :3 brks :R8	60-80cm	10%	1Cfr	215.6m²
EUOEPS	Euonymus europaeus	1+1 :3 brks :R8	60-80cm	5%	1Cfr	107.8m²
ILEAQ	Ilex aquifolium	Bushy :3/5 brks :C 3L	60-80cm	5%	1Cfr	107.8m²
LIGUVI	Ligustrum vulgare	Bushy :C 2L	60-80cm	15%	1Cfr	323.4m²
RHACA	Rhamnus cathartica	1+1 :3 brks :R8	60-80cm	10%	1Cfr	215.6m²
ROSCA	Rosa canina	1+1 :3 brks :R8	60-80cm	3%	1Cfr	67.3m²
ROSRUG	Rosa rugosa	1+1 :3 brks :R8	60-80cm	2%	1Cfr	43.11m²
VIBOP	Viburnum opulus	1+1 :3 brks :R8	60-80cm	10%	1Cfr	215.6m²
						Total :2155.99m² Total :2180
Native Scrub Planting Mix (Thornless)						
Abbr	Species	Supply	Height	Mix	Density	Area Number
CORSA	Cornus sanguinea	1+1 :3 brks :R8	60-80cm	20%	1Cfr	99.11m²
CORAV	Cornus avellana	1+1 :3 brks :R8	60-80cm	30%	1Cfr	148.66m²
CYTSC	Cytisus scoparius	1+1 :3 brks :R8	60-80cm	10%	1Cfr	49.56m²
EUOEPS	Euonymus europaeus	1+1 :3 brks :R8	60-80cm	10%	1Cfr	49.56m²
LIGUVI	Ligustrum vulgare	Bushy :C 2L	60-80cm	20%	1Cfr	101.10m²
VIBOP	Viburnum opulus	1+1 :3 brks :R8	60-80cm	10%	1Cfr	49.56m²
						Total :495.56m² Total :509
Naturalised Bulbs						
Abbr	Species	Specification	Density	Number		
ANEBLBE	Anemone blanda blue flowered	Bulb	10/m²	281		
GALNI	Galanthus nivalis	Bulb	10/m²	281		
HYANSC	Hyacinthoides non-scripta	Bulb	10/m²	281		
MUSARBS	Muscari armeniacum 'Blue Spire'	Bulb	10/m²	281		
						Total :1124
Marginal / Aquatics						
Abbr	Species	Supply	Pot Size	Density	Area	Number
FLUL	Filipendula ulmaria	Well Rooted	195cc min. 150mm	15m²	9.34m²	142
IRIPS	Iris pseudacorus	Well Rooted	195cc min. 150mm	15m²	21.81m²	329
JUNEF	Juncus effusus	Well Rooted	195cc min. 150mm	15m²	21.81m²	329
MYOSCC	Myosotis scorpioides	Well Rooted	195cc min. 150mm	15m²	9.34m²	142
						Total :62.3m² Total :942

Drawing to be read in conjunction with GL2024 SP 01 Landscape Specification.

Turf Areas		Rough Grassland	
Seed Mix Name	Seed Mix Supplier	Seed Mix Name	Seed Mix Supplier
Medallion turf	Rowland Ltd	EM10 Tussock Meadow Mixture	Emorsgate Seeds
		Density	4g/m²
Amenity Grassland Areas		Finch and Bunting (CSS10/FCB)	
Seed Mix Name	Seed Mix Supplier	Seed Mix Name	Seed Mix Supplier
EL1 - Flowering Lawn Mix	Emorsgate Seeds	ABP 1 Year Wild Bird Mix	Boston Seeds
		Density	5g/m²
Amenity Meadow Areas		SuDS Base Meadow Grassland	
Seed Mix Name	Seed Mix Supplier	Seed Mix Name	Seed Mix Supplier
EM6 - Chalk & Limestone Soil	Emorsgate Seeds	EP1 - Pond Edge Mixture	Emorsgate Seeds
		Density	4g/m²
SuDS Banks Meadow Grassland		SuDS Banks Meadow Grassland	
Seed Mix Name	Seed Mix Supplier	Seed Mix Name	Seed Mix Supplier
EMB - Meadow Mixture for Wet Soil	Emorsgate Seeds	EMB - Meadow Mixture for Wet Soil	Emorsgate Seeds
		Density	4g/m²



Marginal / Aquatics		Fot Size		Density Area		Number	
Abbr	Species	Supply	Fot Size	Density	Area	Number	
RLUL	Filipendula ulmaria	Well Rooted	195cc min.	15/m²	9.34m²	142	
RIPS	Iris pseudacorus	Well Rooted	195cc min.	15/m²	21.81m²	329	
JUNEJ	Juncus effusus	Well Rooted	195cc min.	15/m²	21.81m²	329	
MYOSC	Myosotis scorpioides	Well Rooted	195cc min.	15/m²	9.34m²	142	
				Total :62.3m²		Total :942	

Drawing to be read in conjunction with GL2024 SP 01 Landscape Specification

Location Plan

Rev	Date	Notes
0	12/02/22	
1	16/02/25	Revised to the latest planning board, updated to the latest DPA comments.

Int. AL

Project

Highover Farm, Hitchin,
North Hertfordshire

Drawing title

POS Landscape Proposal
(Sheet 1 of 5)

Status

PLANNING

Client

BDW North Thames

Scale

1:250 @ A0

Drawn by

AL

Checked







HJ

Date

23/05/2025

Reference

GL2024 LP 17



Abbr	Species	Pot Size	Height	Habit	Number
FATJAPA	Fatsia japonica	20L	150-175cm	Bushy	1
PHOWAVA	Phormium 'Yellow Wave'	25L	100-125cm	Triple Crown	3
					Total: 4

Native Mix Species Hedgerow						
Abbrev	Species	Supply	Height	Density	Mix %	Number
CORAV	<i>Corvus avallana</i>	1+1.3 brks 3R	60-80cm	0.4CR Double Staggered at 0.4m off	25%	9
CRAMON	<i>Crataegus monogyna</i>	1+1.3 brks 3R	60-80cm	0.4CR Double Staggered at 0.4m off	50%	18
CORSA	<i>Cornus sericea</i>	30-60cm	0.4CR	0.4CR Double Staggered at 0.4m off	25%	9
ILEAQ	<i>Ilex aquifolium</i>	Bushy 3L	40-60cm	0.4CR Double Staggered at 0.4m off	5%	2
VIBOP	<i>Viburnum opulus</i>	1+1.3 brks 3R	60-80cm	0.4CR Double Staggered at 0.4m off	10%	4
LONPE	<i>Lonicera periclymenum</i>	Branched/Caned 3L	60-80cm	0.4CR Double Staggered at 0.4m off	2%	1
ROSCA	<i>Rosa canina</i>	1+1.3 brks 3R	60-80cm	0.4CR Double Staggered at 0.4m off	3%	1

Shrubs - Site Entrance		Pot Size	Height	Habit	Density	Number
Abbr	Species					
CAREVT	<i>Carex oshimensis</i> 'Everest'	5L		Full Pot	0.5Cr	42
HEUMIPP	<i>Heuchera micrantha</i> 'Palace Purple'	5L		Full Pot	0.5Cr	13
HEBPIS	<i>Hebe pinguifolia</i> 'Sutherlandi'	10L	30-40cm	Bushy	0.6Cr	54
MISSIKLF	<i>Miscanthus sinensis</i> 'Black Fontane'	5L		Full Pot	0.6Cr	32
PHOPLBL	<i>Phormium</i> 'Platt's Black'	10L	60-80cm	Triple crown	0.7Cr	38

Herbaceous Grasses						
Abbr	Species	Pot Size	Height	Habit	Density	Number
DESCA	<i>Deschampsia caespitosa</i>	3L		Full Pot	0.5C/tr	331
DESCGU	<i>Deschampsia caespitosa</i> 'Goldstar'	3L		Full Pot	0.5C/tr	511
LUXIVA	<i>Luzula nivea</i>			Full Pot	0.5C/tr	249
MISIML	<i>Miscanthus sinensis</i> 'Morning Light'	3L		Full Pot	0.5C/tr	485
						Total :1576

Abbr	Species	Supply	Height	Misc	Density	Area	Number
ACCA	Acer campestre	1+2 Whip 5 b's 3R: 125-150cm	5%	1CtR		505.05m ²	506
ALNG	Alnus glutinosa	1+2 Whip 3 b's 3R: 125-150cm	3%	1CtR		303.65m ²	304
BETU	Betula pendula	1+2 Whip 3 b's 3R: 125-150cm	3%	1CtR		202.24m ²	203
CARBETA	Carpinus betulus	1+2 Whip 4 b's 3R: 125-150cm	5%	1CtR		505.05m ²	506
CORSANA	Cornus sanguinea	1+1 3 b's 3R: 60-80cm	10%	1CtR		1010.2m ²	1011
CORAVEA	Corylus avellana	1+1 3 b's 3R: 60-80cm	10%	1CtR		1515.29m ²	1516
CROWN	Cotoneaster integrifolius	1+1 3 b's 3R: 60-80cm	10%	1CtR		303.65m ²	304
LONPER	Lonicera periclymenum	Bushy C 2L	60-80cm	2%	1CtR	202.24m ²	203
MASY	Malus sylvestris	1+2 Whip 4 b's 3R: 125-150cm	3%	1CtR		303.65m ²	304
PRAV	Prunus avium	1+2 Whip 4 b's 3R: 125-150cm	2%	1CtR		202.24m ²	203
PRUSPIR	Prunus spinosa	1+1 3 b's 3R: 60-80cm	10%	1CtR		303.65m ²	304
QURO	Quercus robur	1+2 Whip 4 b's 3R: 125-150cm	5%	1CtR		505.05m ²	506
ROSCA	Rosa canina	1+1 3 b's 3R: 60-80cm	3%	1CtR		303.65m ²	304
VIBOPUA	Viburnum opulus	1+1 3 b's 3R: 60-80cm	5%	1CtR		505.05m ²	506

Native Scrub Planting Mix						
	Species	Supply	Height	Mix	Density Area	Number
CORA	Cornus sanguinea	1+1 :3 brks :BR	40-80cm	15% 1Cr	323.4m ²	325
CORAV	Corylus avellana	1+1 :3 brks :BR	60-80cm	25% 1Cr	539.01m ²	542
CYSC	Cytisus scopula	1+1 :3 brks :BR	60-80cm	10% 1Cr	215.6m ²	218
EOEUF	Eumonym europaeus	1+1 :3 brks :BR	60-80cm	5% 1Cr	107.8m ²	111
LEAQ	leuc aquilum	Bushy :3/5 brks :C 3L	60-80cm	5% 1Cr	107.8m ²	111
LIGU	Ligustrum vulgare	Bushy :C 2L	60-80cm	10% 1Cr	323.4m ²	325
RHACA	Rhamnus cathartica	1+1 :3 brks :BR	60-80cm	10% 1Cr	215.6m ²	218
ROSCA	Rosa carolina	1+1 :3 brks :BR	60-80cm	3% 1Cr	64.67m ²	67
ROSRU	Rosa rugosa	1+1 :3 brks :BR	60-80cm	2% 1Cr	43.11m ²	45
VIBOP	Viburnum opulus	1+1 :3 brks :BR	60-80cm	10% 1Cr	215.6m ²	218


Native Scrub planting mix (thornless)							
Abbr	Species	Supply	Height	Mix	Density	Area	Number
CORSA	Cordia sanguinea	+1+3 brks :BR	60-80cm	20% 1CR	99	11m ²	101
CORV	Corylia avellana	+1+3 brks :BR	60-80cm	30% 1CR	99	148.66m ²	151
CYSC	Cytilus scoparius	+1+3 brks :BR	60-80cm	10% 1CR	99	45.56m ²	52
EUPERS	Eunonymus europaeus	+1+3 brks :BR	60-80cm	10% 1CR	99	45.56m ²	52
LIGVU	Ligustrum vulgare	Bushy :C 2L	60-80cm	20% 1CR	99	99.11m ²	101
VIBOP	Viburnum opulus	+1+3 brks :BR	60-80cm	10% 1CR	99	45.56m ²	52

12pals : 49% 4.6m²


13pals : 50%


Naturalised Species				
Abbreviation	Bulbs	Specification	Density	Number
ANBLBF	Anemone blanda blue flowered	Bulb	10/m ²	281
GALNII	Galanthus nivalis	Bulb	10/m ²	281
HYANSC	Hyacinthoides non-scripta	Bulb	10/m ²	281
MUSARBS	Muscari armeniacum "Blue Spire"	Bulb	10/m ²	281
				Total : 1124

Abbr	Species	Supply	Pot Size	Density	Area	Number
FLUL	<i>Filipendula ulmaria</i>	Well Rooted	195cc min.	15/m ²	9.34m ²	142
IRPS	<i>Iris pseudacorus</i>	Well Rooted	195cc min.	15/m ²	21.81m ²	329
JUNE	<i>Juncus effusus</i>	Well Rooted	195cc min.	15/m ²	21.81m ²	329
MYOS	<i>Myosotis scorpioides</i>	Well Rooted	195cc min.	15/m ²	9.34m ²	142
Total :62.3m ² Total :942						



Drawing to be read in conjunction with GL2024 SP 01 Landscape Specification.






For **ecology enhancements** please refer to the Landscape and Ecological Management and Enhancements document, which forms part of the site wide OLEMP.

Marginal / Aquatics						
Abbr	Species	Supply	Pot Size	Density	Area	Number
FILUL	Filipendula ulmaria	Well Rooted	195cc min.	15/m ²	9.34m ²	142
IRIPS	Iris pseudacorus	Well Rooted	195cc min.	15/m ²	21.81m ²	329
JUNEF	Juncus effusus	Well Rooted	195cc min.	15/m ²	21.81m ²	329
MYOSC	Myosotis scorpioides	Well Rooted	195cc min.	15/m ²	9.34m ²	142
					Total :62.3m ²	Total :942

Drawing to be read in conjunction with GL2024 SP 01 Landscape Specification.

Location Plan	Rev	Date	Notes	Int	Project
	A	19/03/23	Updated to the latest LPA comments.	AL	Highover Farm, Hitchin, North Hertfordshire
Drawing title POS Landscape Proposals [ph1] (Sheet 3 of 3)					
Status PLANNING					
Client BDW North Thames					
Scale 1:250 @ A0		Drawn By AL		Checked By HJ	
Date 23/05/2025		Reference GL2024 LP 19A			
					



Tel: 01530 265688 Web: www.golbyandluck.co.uk

Email: info@golbyandluck.co.uk

Midlands: 207 Leicester Road, Ibstock, Leicestershire, LE67 6HP
York: Suite 2.2, Innovation Centre, Innovation Way, York, YO10 5NY

Golby and Luck LTD (Company No. 9037776) Registered in England and Wales