

COLOUR REFERENCING (AND EUROPEAN STANDARD)	
 	New construction
 	Item(s) retained in existing location
 	New item(s)
 	Relocated item(s)
 	Merchandising items
 	Optional/future item(s)

NOTES:

All drawings to be read in conjunction with all other drawings.

All dimensions and levels to be checked on site.

Any discrepancies to be reported to the architect before any work commences. Do not scale off drawings.

This drawing shall not be reproduced without express written permission from C7.

The overlay drawings and ownership boundaries are produced using all reasonable endeavours. C7 cannot be held responsible for the accuracy or scale discrepancy of base plans supplied to them.

All works to be undertaken within current Building Regulation Approved Doc's, British Standards and appropriate codes of practice.

All proprietary materials and products are to be used strictly in accordance with the manufacturers recommendations.

All equipment and lifts to be surveyed on site by Contractor and Sub Contractors prior to manufacture and installation.

KEY: ID TAGS - MERCHANDISING	
SOK's	Self Ordering Kiosk
ORB	Order Ready Board
PAM	Public Awareness Monitor
PRICE	Price Menu
HMU	Happy Meal Unit
DP	Digital Poster
HC	High Chair
PROMO	Promotional Screens

Notes :

- Existing RMHC Drive-thru boxes must be retained & replaced with any cashier booth work or a new installed will be charged to the contractor.
- Refer to standard installation details for all digital Merchandising screens.
- Contractor to assess quality of substrate and line out walls if necessary for Vinyl graphics

H&K TO PROVIDE FINAL KITCHEN LAYOUT & DETAILS

H&K Kitchen Layout:
Drawing No: DIN-XXX REV X

KITCHEN:

- New 600x600mm Metal Pan suspended ceiling grid & tiles with new flat panel LED lights - CDM Partnership to provide lighting layout.
- Existing floor tiles retained & made good with new to match existing in altered areas
- Existing White Rock wall finish made good with new to altered areas

KITCHEN EQUIPMENT:

- New H&S Prep Line with 4HP's
- New ABS
- 4 No. Existing Coffee machines
- 1 No. Existing & relocated BIC
- 1 No. Existing & relocated Shake Machine
- 1 No. Existing Flurry Freezer
- New 1500mm Wash-Up Sink
- New Jeros Dishwasher

COURIER ROOM:

- New floor & wall finishes to match restaurant decor
- New 1200x600mm Rockfon ceiling grid & acoustic tile suspended ceiling to match restaurant decor with new J1 LED ceiling lights
- New standard 1200mm flat counter
- 1 No. ORB in bulkhead above counter
- 1 No. PAM Screen
- 1 No. Power & USB Socket above bench height
- 1 No. New landing table
- Include music speaker
- Ensure WIFI signal
- New aluminium frame 826mm leaf entrance door with 'McDelivery Partners Only' Signage & Opague film applied.
- Internal Shopfront spray to match decor scheme of restaurant
- Opague film to shopfront window

GENERAL ARRANGMENT PLAN - DINING ROOM

1:50

0 1.25m 2.5m 3.75m 5.0m

AREA SCHEDULE		
	EXISTING	PROPOSED
Total Covers	73	81
Dining Area Ground	100 m ²	102 m ²
Customer WC	25 m ²	23 m ²
Crew Room	14 m ²	14 m ²
Crew WC	12 m ²	12 m ²

ESSENTIAL INGREDIENTS 2.0 RE-IMAGE

DESIGN WORKING GROUP APPROVED

1	12.12.2024	Initial Design Review Meeting	LP	14
2	18.12.2024	Validation of P&ID's submitted	DM	15
3	20.12.2024	Final Review	LP	16

Name (P/N):
Signature: Date:

GENERAL NOTES:
All works are to be undertaken in accordance with the Building Regulations and the latest British Standards.
All proprietary materials and products are to be used strictly in accordance with the manufacturers recommendations.
All dimensions to be checked on site prior to construction.

PROJECT LOCATION:
McDonald's Restaurants Ltd
A505 Baldock Road
Royston SG8 9NT

PROJECT TITLE:
General Arrangement Plan
ESSENTIAL INGREDIENTS 2.0 DECOR

REVISIONS:
REV: 1
DATE: 20.01.2026
BY: [Signature]
CHECKED: [Signature]
APPROVED: [Signature]

McDonald's Restaurants Ltd
Royston SG8 9NT

McDonald's Restaurants Ltd
Royston SG8 9NT

McDonald's Restaurants Ltd
Royston SG8 9NT