FOR CONTINUATION REFER TO SHEET 8

FOR CONTINUATION REFER TO SHEET 8

FOR CONTINUATION REFER TO SHEET 2

FOR CONTINUATION REFER TO SHEET 2

FOR CONTINUATION REFER TO SHEET 6

ELM HEDGE HT 5m

HORSE CHESTNUT G 0.8 HT 7m

MAPLE G 1.0 HT 9m

WHITEBEAM G 1.5 HT 7m

ASH G 1.0 HT 9m

SCRUB HT 3m

CHERRY G 0.7 HT 7m

SILVER BIRCHES G 0.5 HT 7m

OAK G 1.6 HT 7m

MAPLE G 1.0 HT 12m

DEAD G 0.6 HT 8m

ASH G 0.7 HT 12m

ELM G 0.5 HT 8m

GATE

7.33

MAPLE G 1.0 HT 11m

ASH G 0.7 HT 12m

ELM G 0.6 HT 7m

FIELD MAPLE G 0.7 HT 8m

MAPLE G 0.8 HT 11m

STONE LAY-BY

MAPLE G 1.0 HT 11m

ASH G 1.0 HT 11m

LIME G 0.9 HT 12m

MIXED HEDGE HT 4m

GRASS/SCRUB

GRASS/SCRUB

STOTFOLD ROAD

S278 WORKS

PLOTS D1-4

PLOTS D17-18

Phoenix 2 Duo Recycler (P2-15W with Elite 6x4 chassis)

Phoenix 2 Duo Recycler (P2-15W with Elite 6x4 chassis)

Phoenix 2 Duo Recycler (P2-15W with Elite 6x4 chassis)


Phoenix 2 Duo Recycler (P2-15W with Elite 6x4 chassis)

UNTIL TECHNICAL APPROVAL HAS BEEN OBTAINED FROM THE RELEVANT LOCAL AUTHORITIES OR STATUTORY BODIES, IT SHOULD BE UNDERSTOOD THAT ALL DRAWINGS ARE ISSUED AS PRELIMINARY AND NOT FOR CONSTRUCTION. SHOULD THE CONTRACTOR AND / OR EMPLOYER COMMENCE WORK PRIOR TO APPROVAL BEING GIVEN, IT IS ENTIRELY AT THEIR OWN RISK

NOTES:


DO NOT SCALE

1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
2. ALL LEVELS ARE IN METRES ABOVE ORDNANCE DATUM.
3. DRAWING BASED ON TOPOGRAPHICAL SURVEY BY MK SURVEYS DATED AUGUST 2022
4. ALL WORKS TO BE UNDERTAKEN IN ACCORDANCE WITH THE SPECIFICATION FOR HIGHWAY WORKS (SHW), HERTFORDSHIRE COUNCIL STANDARD DETAILS.
5. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT DRAWINGS AND DETAILS
6. RADIUS KERBS TO BE USED WHERE REQUIRED/APPROPRIATE. WHERE DROPPED KERBS ARE TO BE LAID TO A RADIUS THEY SHALL BE DISC CUT IN HALF TO FORM A MITRE.
7. WHERE THE EXISTING AND PROPOSED KERB/EDGING ARE TO BE TIED IN THEY SHALL BE DISC CUT TO FORM A CLEAN VERTICAL FACE AND CLOSE JOINT.
8. NO OPEN JOINTS WILL BE ACCEPTED, NO CHIPPED, DAMAGED OR REPAIRED KERBS WILL BE ACCEPTED.
9. CONTRACTOR SHOULD PROVIDE MECHANICAL LIFTING AIDS FOR ITEMS HEAVIER THAN 20 KGS. IF MECHANICAL LIFTING AIDS ARE IMPRACTICAL A RISK ASSESSMENT SHOULD BE UNDERTAKEN WHICH IDENTIFIES THE APPROPRIATE CONTROL MEASURES REQUIRED TO AVOID RISK OF INJURY FROM MANUAL HANDLING.
10. CONTRACTOR TO PROVIDE CBR RESULTS TO HCC PRIOR TO COMMENCEMENT OF PAVEMENT WORKS.
11. FOR TYPICAL SECTION DETAILS REFER TO DRAWING HOF-WSP-S278-ZZ-DR-C-07102.



Phoenix 2 Duo Recycler
(P2-15W with Elite 6x4 chassis)

Overall Length	11.220m
Overall Width	2.530m
Overall Body Height	3.756m
Min Body Ground Clearance	0.309m
Track Width	2.530m
Lock-to-lock time	4.00s
Curb to Curb Turning Radius	11.550m



0 12.5 metres

REV	DATE	BY	DESCRIPTION	CHK	APP
P03	27/10/2025	SM	UPDATED TO SUIT REVISED MASTERPLAN	DSB	TP
P02	06/06/2025	DSB	MASTERPLAN UPDATED	DSB	LJM
P01	14/10/2024	MH	FIRST ISSUE	DSB	LJM

DRAWING STATUS:
S2 - FOR INFORMATION

wsp
Unit 9 The Chase, John Tate Road, Foxholes Business Park, Hertford, SG13 7NN, UK
T+ 44 (0) 1992 526 000, F+ 44 (0) 1992 526 001
wsp.com

CLIENT:
BARRATT DAVID WILSON HOMES

ARCHITECT:
MCBAINS

SITE/PROJECT:
HIGHOVER FARM, HITCHIN

TITLE:
PHASE 1
REFUSE TRACKING
SHEET 3 OF 8

SCALE @ A1:	CHECKED:	APPROVED:
1:250	DSB	LJM

PROJECT NO:	DESIGNED:	DRAWN:	DATE:
700982227	RH	RH	October 25

DRAWING No: HOF-WSP-ZZ-PH1-DR-C-1553 REV: P03

© WSP UK Ltd

File name C:\DEV\WSP\O365\UK K2RC DEVELOPMENT - 700982227 - HIGHOVER FARM, HITCHIN - DETAILED DESIGN\03 WIP\CIV CIVIL ENGINEERING\01 DRAWINGS\PH1 DETAILED DESIGN\HOF-WSP-ZZ-PH1-DR-C-1553.DWG, printed on 28 October 2025 12:22:37, by Ankitaj, Shandhan