

Project: Stevenage Road / Sperberry Hill, St. Ippolyts
Job No: 5761 – 2376 – Plots 7 & 10
Date: March 2025
Revision: 2

SCHEDULE OF EXTERNAL MATERIALS

RESIDENTIAL ELEMENT	MATERIAL/MANUFACTURER/TYPE/FINISH
Walls	
Facing Brickwork A	Forterra - Hampton Rural Blend
Lintels and/or Cill	Pebble Grey Timber Lintel & Pre-cast concrete cill
UPVC rain water goods	Black, half-round gutter and downpipes
Windows and External Doors	
Double glazed UPVC window	Pebble Grey
Front Door – Composite – RAL Pebble Grey external, RAL White 9010 Internal – double toughened glazing	Pebble Grey
Rear/Bi-Folding Doors – Composite – RAL Anthracite 7016 – double toughened glazing	Anthracite
Roof	
Roof Tile	Russell Concrete Peat Brown
Canopy	Pitched Timber Canopy, with brick plinth to match facing material
Chimney	Traditional - Forterra - Hampton Rural Blend

PHOTOGRAPHIC SAMPLES

Facing Brick – Forterra – Hampton Rural Blend	
Lintel - Pebble Grey Timber	
Cill – Pre-cast Concrete	
uPVC Half-round Gutter & Downpipes - Black	

Double Glazed Windows - uPVC	
Front Door - Front Door – Composite – RAL Pebble Grey external, RAL White 9010 Internal – double toughened glazing	
Roof Tile - Russell Concrete Peat Brown	
Canopy - Pitched Timber Canopy, with brick plinth to match facing material	
Rear Door - Rear/Bi-Folding Doors – Composite – RAL Anthracite 7016 – double toughened glazing	
Chimney - Traditional	

SCHEDULE OF REVISIONS		
Date	Issue	Amendment
18.12.2024	1	Initial Issue
17.03.2025	2	Canopy Updated