

Project: Fl Stevenage Road / Sperberry Hill, St. Ippolyts
Job No: 5761 – 2376 – Plots 6 & 8
Date: March 2025
Revision: 2

SCHEDULE OF EXTERNAL MATERIALS

RESIDENTIAL ELEMENT	MATERIAL/MANUFACTURER/TYPE/FINISH
Walls	
Facing Brickwork A	Buff Recon Stone
Lintels and/or Cill	Pebble Grey Timber Lintel & Pre-cast concrete cill
UPVC rain water goods	Black, half-round gutter and downpipes
Windows and External Doors	
Double glazed UPVC window	Anthracite
Front Door – Composite – RAL BLACK external, RAL White 9010 Internal – double toughened glazing	Black
Rear/Bi-Folding Doors – Composite – RAL Anthracite 7016 – double toughened glazing	Anthracite
Front Door Surround	Polyester Powder Coated Pebble Grey
Roof	
Roof Tile	Marley Modern Concrete Grey
Canopy	Pitched Timber Canopy, with stone plinth to match facing material
Chimney	Traditional

PHOTOGRAPHIC SAMPLES

Facing Brick – Buff Recon Stone	
Lintel - Pebble Grey Timber	
Cill – Pre-cast Concrete	

uPVC Half-round Gutter & Downpipes - Black	
Double Glazed Windows - uPVC	
Front Door - Front Door – Composite – RAL BLACK external, RAL White 9010 Internal – double toughened glazing	
Roof Tile - Marley Modern Concrete Grey	
Canopy – Pitched Timber Canopy, with stone plinth to match facing material	
Rear Door - Rear/Bi-Folding Doors – Composite – RAL Anthracite 7016 – double toughened glazing	

Chimney - Traditional



SCHEDULE OF REVISIONS

Date	Issue	Amendment
18.12.2024	1	Initial Issue
17.03.2025	2	Canopy Updated