

NOTES

PROJ No. B-P1219-1
BTEE No. 16849
H3G No. HRT0230
MBNL No. NHE059

PROJ No			
PROJ No			
PROJ No			
PROJ No	B-P1219-1		
B	MINOR AMENDMENT	03/06/25	SAM
A	PROJ No B-P1219-1 PLANNING		WHP
ISS	REVISION	DATE	DRN APP



SITE No P1219
ST IPPOLLYTTS - POUND FARM SP
OFF LONDON ROAD
HITCHIN
STEVENAGE
SG4 7NF

NGR TL19382 27467

OS GRID 519382 227467

TITLE
EQUIPMENT PLAN
PROPOSED
H3G & BTEE LTD

SCALE 1:50

DRAWN	WHP	05/03/25
APPROVED		

WIG DRG No.	Sheet 1 of 1	Rev
P1219-02-101-MD001		B



NOTE: SITE TO BE CLEARED OF VEGETATION
PRIOR TO WORKS TAKING PLACE

EXISTING H3G & BTEE 6No. LDF5-50 FEEDERS TO BE REMOVED. EXISTING H3G & BTEE 6No. LDF5-50
FEEDERS TO BE REUSED (SUBJECT TO TESTING). PROPOSED BTEE 3No. SINGLE MODE FIBRE
CABLES & 3No. 10mm 8C DC CABLES TO BE INSTALLED ON EXISTING WIG CABLE MANAGEMENT

PROPOSED BTEE 3No. Mk2 BOB's TO BE INSTALLED
ON EXISTING WIG GANTRY SUPPORT POLE

BTEE 1No. BTS3900A CABINET TO BE REMOVED

PROPOSED BTEE 1No. AC AIRO CABINET TO BE INSTALLED
c/w DC PSU ON EXISTING WIG CONCRETE BASE

H3G & BTEE 300mm WIDE SURFACE CABLE TRAY

PROPOSED BTEE 1No. GPS AT 3.0m AGL TO BE
INSTALLED ON WIG GANTRY SUPPORT POLE

H3G & BTEE 1No. NODE B CABINET
ON WIG CONCRETE BASE

H3G & BTEE 1No. TX CABINET
ON WIG CONCRETE BASE

H3G & BTEE 300mm WIDE CABLE LADDER

H3G & BTEE 600mm WIDE CABLE LADDER

H3G & BTEE 1No. PSU ON
WIG CONCRETE BASE

H3G & BTEE EQUIPMENT LAYOUT

