

Top View - 1:50

Exit Loop

Front Elevation - 1:50

Rear Elevation - 1:50

3D Front

3D Rear

Scale Bar 1:50

Autogate Services & Installations Ltd
Unit 14 Wyndmere Park,
Ashwell Road,
Steeple Morden,
Hertfordshire,
SG8 0NZ
01763853663



SITE ADDRESS
Townsend House 109 High
Street Barkway Royston
Herts
SG8 8ED

ISSUE
20.10.2025

DRAWN BY	CHECKED BY	PROJECT NO.
KAA	WB	32070
REV		GATESTYLE
A		<i>Barkway</i>
DESCRIPTION		SCALE
Planning Approval		As stated @ A3

PAGE

02

- ## Notes

1. Gates will be installed 7m away from road.
2. Gates will be hang off 150mm x 150mm posts.
3. Post to post will be (inside 2900mm) and (outside 3200mm).
4. Ground level to top of railheads will be as shown in front elevation.
5. Gates in open position width will be 2710mm as shown in top view.
6. The framework will be powder coated and finished in RAL 9005, satin black.
7. This is the gate, this gate will be have exit loop installed 4m away on the property side.
8. The rear elevation shows details of each leaf will be made up too (W1380mm x H1750mm to raise up to H2050mm).