

APPENDIX 2 : SURVEY SCHEDULE (page 1 of 2)

Tree ID.	Species (Common Name)	Age Class	Height (m)	Crown Spread (m)				Crown Clearance (m)	Stem dia. (mm)	Vigour	Amenity Value	Condition	Observations / Comments	Recommendations	Ret. Cat. (Sub cat.)	RPA (m)
				North	East	South	West									
T1	<i>Sorbus aria</i> (Whitebeam)	Semi-mature	6	2.5	3	3	2.2	2	230	Normal	Low	Good	No observations / comments	No action required	C	2.8
T2	<i>Prunus padus</i> (Bird Cherry)	Semi-mature	4	2	2	2	1.5	0.1	4 x 100	Normal	Low	Good	Previously reduced to 2m. Ivy clad main stem	Remove to facilitate construction access	C	(2.4)
T3	<i>Prunus padus</i> (Bird Cherry)	Semi-mature	5	2	2	2	1.5	0.4	4 x 80	Normal	Low	Good	Previously reduced to 2m. Ivy clad main stem	Remove to facilitate construction access	C	(1.9)
T4	<i>Acer pseudoplatanus</i> (Sycamore)	Semi-mature	12	5	4	3	5.5	2.5	330	Normal	Low	Good	Ivy clad throughout crown	Remove to facilitate construction access	C	(4.0)
T5	<i>Fraxinus excelsior</i> (Common Ash)	Mature	18	6	6	7	8.5	4	670	Normal	Low	Fair	Height previously reduced. Visible decay to upper main stem. Significant deadwood throughout crown	Remove all significant deadwood	B (1)	8.0
T6	<i>Fraxinus excelsior</i> (Common Ash)	Mature	17	7	6	6.5	4	3	600	Normal	Low	Fair	Ivy clad throughout crown. Significant deadwood throughout crown	Remove all significant deadwood	B (1)	7.2
T7	<i>Juglans regia</i> (English Walnut)	Semi-mature	2.5	1	1	1	1	0	10 x 20	Normal	Low	Poor	Original tree removed (stump remaining), sucker re-growth from stump	REMOVE	U	n/a
T8	<i>Juglans regia</i> (English Walnut)	Semi-mature	9	4	6	3.5	5	1	300	Normal	Low	Good	Low crown	Crown lift on south side to 3m, to facilitate new access	B (2)	3.6
T9	<i>Juglans regia</i> (English Walnut)	Semi-mature	7	3.5	3.5	2.5	3.5	4	230	Normal	Low	Good	No observations / comments	No action required	B (2)	2.8