

BTEE 6No. LDF5-50 FEEDERS TO BE REMOVED. H3G 12No. LDF78-50 FEEDERS TO BE REUSED (SUBJECT TO TESTING). PROPOSED BTEE 3No. 8-CORE SINGLE MODE FIBRE & 3No. 8-CORE DC CABLES TO BE INSTALLED



H3G & BTEE 1No. EQUIPMENT CABIN ON CONCRETE BASE TO BE REFRESHED FOR PROPOSED UPGRADE

PROPOSED BTEE 1No. AIRI CABINET C/W AMIA BBU TO BE INSTALLED WITHIN EQUIPMENT CABIN

BTEE 1No. BTS3900L CABINET TO BE REMOVED

PROPOSED BTEE 3No. COMMSCOPE MK2 BOB's TO BE INSTALLED ON PROPOSED VERTICAL CABLE LADDER WITHIN EQUIPMENT CABIN

H3G & BTEE 1No. CRABTREE WALL MOUNTED AC DISTRIBUTION BOARD TO BE UPGRADED WITH ICD 11775 PAN ASSEMBLY KIT

H3G & BTEE 1No. ELTEK PSU CABINET C/W 3No. 2kW RECTIFIERS TO BE REUSED FOR UPGRADE. ADDITIONAL 5No. 2kW RECTIFIERS REQUIRED (8No. 2kW RECTIFIERS IN TOTAL)

PROPOSED BTEE 1No. UHF GPS NODE AT 3.0m MEAN I.D. No. TBC TO BE INSTALLED ON GANTRY POLE

1.8m HIGH CHAINLINK FENCE WITH 3No. STRANDS OF BARBED WIRE

30.0m HIGH TOWER

BTEE 1No. METER CABINET 1 (REDUNDANT) ON CONCRETE BASE


BTEE 1No. CABINET 3 (REDUNDANT) ON CONCRETE BASE

BTEE 1No. CABINET 4 (REDUNDANT) ON CONCRETE BASE

BTEE 1No. CABINET 5 (REDUNDANT) ON CONCRETE BASE

BTEE 1No. CABINET 6 (REDUNDANT) ON CONCRETE BASE

H3G & BTEE METER CABINET 3 ON CONCRETE BASE C/W THREE PHASE 100A REC SUPPLY



FEINT DETAILS INDICATE LOCATIONS RESERVED FOR OTHER PROPOSALS WHICH MAY BE THE SUBJECT OF SEPARATE APPLICATIONS

©2020 Cellnex
All rights reserved. No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means (Electronic, Mechanical, Photocopying, Recording or otherwise), without the prior written consent of the Company.

NOTES

THIS DESIGN COMPLIES WITH CELLNEX ICNIRP STANDARD UK-DE_PRO-0020 v7

NOTE:
PRO X5 COMPLETED ON 11/09/2024 AND DEEMS THAT THE SITE ACHIEVES ICNIRP COMPLIANCE

PROJECT No. COLMOD.UK.0003737

CELL No. SVG011

BTEE ID. 90336

10.A	COLMOD.UK.0003737 PLANNING		GBC	
10	COM-0014261 PROJECT REMOVAL	26/02/24	MCD	MCD
9	243476 PLANNING DRAWING	08/12/21	BEA	BEA
8	214299 DECOM	30/05/19	BB	MF
7	177732 AS BUILT	22/03/17	WHP	JW
ISS	REVISION	DATE	DRN	APP



CELLNEX UK
R+, 4TH FLOOR, 2 BLA GRAVE STREET, READING, RG1 1AZ
Tel. 020 4526 8553

SITE No 1490336

WATTON SUB STATION
WATTON ROAD
KNEBWORTH
STEVENAGE
HERTFORDSHIRE
SG3 6AG

NGR TL 25679 20500

OS GRID 525679 220500

TITLE
SITE PLAN
PROPOSED
H3G & BTEE LTD

SCALE 1:100

DRAWN	IM	19/08/11
APPROVED	MCD	26/02/24

DRG No.	Sheet 1 of 1	Rev
1490336-02-110-MD010	10.A	