

9-10 High Street Hitchin



Noise Impact Assessment Report
Report 25713.NIA.02. RevB

Tigg Coll Architects

Report 25713.NIA.02. RevB			
Revision History			
First Issue Date: 07/05/2023			
A	14/05/2024 Overheating section updated – detailed assessment for each façade	D	
B	06/06/2024 Overheating section updated to coordinate with the findings of the overheating analysis carried out by Integration Consultancy Limited	E	
C		F	
Written by:		Checked by:	Approved by:
Thomas Bergmanis AMIOA Acoustic Consultant		Jacob Tyler MIOA Senior Acoustic Consultant	John Cane MIOA Senior Acoustic Consultant
Disclaimer KP Acoustics Ltd. has used reasonable skill and care to complete this technical document, within the terms of its brief and contract with the resources devoted to it by agreement with the client. We disclaim any responsibility to the client and others in respect of any matters outside the stated scope. This report is confidential to the client and we accept no responsibility to third parties to whom this report, or any part thereof, is made known. KP Acoustics Ltd. accepts no responsibility for data provided by other bodies and no legal liability arising from the use by other persons of data or opinions contained in this report. KP Acoustics Ltd. 2024			

Contents

1.0	INTRODUCTION.....	1
2.0	SITE SURVEYS	1
2.1	Site Description	1
2.2	Environmental Noise Survey Procedure	1
2.3	Measurement Positions	1
2.4	Equipment.....	2
3.0	RESULTS.....	3
4.0	NOISE ASSESSMENT GUIDANCE.....	4
4.1	Noise Policy Statement for England 2021.....	4
4.2	Planning Practice Guidance – Noise (PPG-N).....	5
4.3	ProPG: Planning and Noise	6
4.4	BS8233:2014	6
4.5	Approved Document O (ed. 2021).....	7
4.5.1	Application	8
4.5.2	Internal Noise Level Targets.....	8
4.5.3	Methods to Remove Excess Heat	9
5.0	EXTERNAL BUILDING FABRIC SPECIFICATION	9
5.1	Non-Glazed Elements.....	9
5.2	Glazed Elements.....	9
6.0	VENTILATION AND OVERHEATING.....	10
6.1	Ventilation Strategy	10
6.2	Openable Windows.....	11
6.3	Overheating Control Strategies	12
7.0	EXTERNAL AMENITY AREA ASSESSMENT.....	13
8.0	DIRECT NOISE TRANSFER ASSESSMENT.....	14
8.1	Party Floor System – Car Park to Ground Floor Residential	14
8.2	Party Floor System – Retail Unit to Ground Floor Residential.....	14
9.0	PLANT NOISE ASSESSMENT.....	15
9.1	Proposed Plant Installations	15
9.2	Noise Assessment Guidance	15
9.3	Plant Limiting Noise Levels.....	16
9.4	Suitable Suppliers.....	17

9.5	Anti-Vibration Mounting Strategy	17
10.0	NOISE PROPAGATION MODEL	17
10.1	Noise Sensitive Receivers.....	17
10.2	Emergency Plant - Standby Smoke Extract (Ground Floor)	18
11.0	CONCLUSION.....	19

List of Attachments

25713.TH1-2	Environmental Noise Time Histories
25713.Daytime.LA90.TH1-2	Statistical analysis of representative daytime L_{A90}
25713.Night-time.LA90.TH1-2	Statistical analysis of representative night-time L_{A90}
Appendix A	Glossary of Acoustics Terminology
Appendix B	Anti-Vibration Mounting Specification Reference Document

1.0 INTRODUCTION

KP Acoustics Ltd has been commissioned to assess the suitability of the site at 9-10 High Street, Hitchin SG5 1BH for a residential development in accordance with the provisions of the National Planning Policy Framework and the Noise Policy Statement for England (NPSE).

This report presents the results of the environmental survey undertaken in order to measure prevailing background noise levels, followed by calculations in accordance with BS4142 to provide limiting noise levels for the future specified plant items and an indication as to the likelihood of the noise emission from the proposed plant unit installations having an adverse impact on the noise sensitive receptors.

2.0 SITE SURVEYS

2.1 Site Description

The site is bounded by Brand Street and residential properties to the north, the High Street to the east, residential properties to the south and a car park and the A505 to the west. At the time of the survey, the background noise climate was dominated by road traffic noise from surrounding road network.

2.2 Environmental Noise Survey Procedure

A noise survey was undertaken on the proposed site as shown in Figure 2.1. The location was chosen in order to collect data representative of the worst-case levels expected on the site due to all nearby sources.

Continuous automated monitoring was undertaken for the duration of the survey between 13:00 on 11 January 2023 and 13:00 on 12 January 2023.

Weather conditions were generally dry with light winds and therefore suitable for the measurement of environmental noise. The measurement procedure complied with ISO 1996-2:2017 Acoustics '*Description, measurement and assessment of environmental noise - Part 2: Determination of environmental noise levels*'.

2.3 Measurement Positions

Measurement positions are as described within Table 2.1 and shown within Figure 2.1.

Icon	Descriptor	Location Description
	Noise Measurement Position 1	The microphone was installed at roof level along the front, as shown in Figure 2.1. The microphone was positioned within free-field conditions at approximately 1.5 metres from the nearest surface.

Icon	Descriptor	Location Description
	Noise Measurement Position 2	The microphone was installed at roof level, as shown in Figure 2.1. The microphone was located within 1.5 metres of the nearest surface and therefore includes local reflections.

Table 2.1 Measurement positions and descriptions




Figure 2.1 Site measurement positions (Image Source: Google Maps)

2.4 Equipment

The equipment calibration was verified before and after use and no abnormalities were observed. The equipment used is described within Table 2.2.

Measurement instrumentation		Serial no.	Date	Cert no.
Noise Kit 27	NTI Audio XL2 Class 1 Sound Level Meter	A2A-21174-E0	21/07/2022	UK-22-070
	Free-field microphone NTI Acoustics MC230A	A23539		
	Preamp NTI Acoustics MA220	11025		
	NTI Audio External Weatherproof Shroud	-	-	-
Noise Kit 28	NTI Audio XL2 Class 1 Sound Level Meter	A2A-21140-E0	04/08/2022	UK-22-076
	Free-field microphone NTI Acoustics MC230A	A23592		
	Preamp NTI Acoustics MA220	10981		
	NTI Audio External Weatherproof Shroud	-	-	-
Larson Davis CAL200 Class 1 Calibrator		17148	18/03/2022	UCRT22/1397

Table 2.2 Measurement instrumentation

3.0 RESULTS

The $L_{Aeq: 5min}$, $L_{Amax: 5min}$, $L_{A10: 5min}$ and $L_{A90: 5min}$ acoustic parameters were measured throughout the duration of the survey. Measured levels are shown as time histories in Figures 25713.TH1-2.

Measured noise levels are representative of noise exposure levels expected to be experienced by all facades of the proposed development, and are shown in Table 3.1.

Time Period	Noise Measurement Position 1 (Measured Noise level – dBA)	Noise Measurement Position 2 (Measured Noise level – dBA)
Daytime $L_{Aeq,16hour}$ (07:00-23:00)	57	58
Night-time $L_{Aeq,8hour}$ (23:00-07:00)	54	57

Table 3.1 Site average noise levels for daytime and night time

It should be noted that the representative background noise level has been derived by statistical analysis of the occurring $L_{A90,5 min}$ levels measured during the environmental noise survey undertaken on site, as shown in 25713.Daytime.LA90.TH1-2 and 25713.Night-time.LA90.TH1-2 attached. Table 3.2 presents the representative background noise levels measured throughout the duration of the survey.

Time Period	Representative background noise level L_{A90} dB(A)	
	Noise Measurement Position 1	Noise Measurement Position 2
Daytime (07:00-23:00)	52	56
Night-time (23:00-07:00)	45	50

Table 3.2 Representative background noise levels

Please note that Noise Measurement Position 2 is located at a distance less than 1.5 metres from the nearest reflective surface and therefore a 3dB correction has been applied to the results in Table 3.1 and Table 3.2 to obtain a free-field measurement as per ISO1996 Part 2.

4.0 NOISE ASSESSMENT GUIDANCE

4.1 Noise Policy Statement for England 2021

The National Planning Policy Framework (NPPF) has superseded and replaces Planning Policy Guidance Note 24 (PPG24), which previously covered issues relating to noise and planning in England. Paragraph 174 of NPPF 2021 states that planning policies and decisions should aim to:

- preventing new and existing development from contributing to, being put at unacceptable risk from, or being adversely affected by, unacceptable levels of soil, air, water or noise pollution or land instability. Development should, wherever possible, help to improve local environmental conditions such as air and water quality, taking into account relevant information such as river basin management plans

In addition, Paragraph 185 of the NPPF states that *'Planning policies and decisions should also ensure that new development is appropriate for its location taking into account the likely effects (including cumulative effects) of pollution on health, living conditions and the natural environment, as well as the potential sensitivity of the site or the wider area to impacts that could arise from the development. In doing so they should':*

- Mitigate and reduce to a minimum potential adverse impacts resulting from noise from new development – and avoid noise giving rise to significant adverse impacts on health and the quality of life
- Identify and protect tranquil areas which have remained relatively undisturbed by noise and are prized for their recreational and amenity value for this reason

The Noise Policy Statement for England (NPSE) was developed by DEFRA and published in March 2010 with the aim to 'Promote good health and good quality of life through the effective management of noise within the context of Government policy on sustainable development.'

Noise Policy Statement England (NPSE) noise policy aims are as follows:

Through the effective management and control of environmental, neighbour and neighbourhood noise within the context of Government policy on sustainable development.

- *Avoid significant adverse impacts on health and quality of life;*
- *Mitigate and minimise adverse impacts on health and quality of life; and*
- *Where possible, contribute to the improvement of health and quality of life*

The Noise Policy Statement England (NPSE) outlines observed effect levels relating to the above, as follows:

- NOEL – No Observed Effect Level
 - This is the level below which no effect can be detected. In simple terms, below this level, there is no detectable effect on health and quality of life due to the noise.
- LOAEL – Lowest Observed Adverse Effect Level
 - This is the level above which adverse effects on health and quality of life can be detected.
- SOAEL – Significant Observed Adverse Effect Level
 - This is the level above which significant adverse effects on health and quality of life occur.

As stated in The Noise Policy Statement England (NPSE), it is not currently possible to have a single objective based measure that defines SOAEL that is applicable to all sources of noise in all situations. Specific noise levels are not stated within the guidance for this reason, and allow flexibility in the policy until further guidance is available.

4.2 Planning Practice Guidance – Noise (PPG-N)

Planning Practice Guidance – Noise (PPG) was introduced by the Ministry of Housing, Communities & Local Government in March 2014 and revised in July 2019. It is an online digital resource that “advises on how planning can manage potential noise impacts in new development”. It gives guidance on establishing whether noise will likely cause a concern, factors of influence on noise impact and methods by which planning can address adverse effects of noise sources.

A noise exposure hierarchy table is provided within the guidance that follows the same observed effect descriptors given within the NPSE guidance, i.e. NOEL, NOAEL and LOAEL and SOAEL.

For a NOAEL descriptor: “A noise has no adverse effect so long as the exposure does not cause any change in behaviour, attitude or other physiological responses of those affected by it. The noise may slightly affect the acoustic character of an area but not to the extent there is a change in quality of life”

4.3 ProPG: Planning and Noise

As outlined above, the National Planning Policy Framework encourages improved standards of design, although it provides no specific noise levels which should be achieved on site for varying standards of acoustic acceptability, or a prescriptive method for the assessment of noise.

ProPG: Planning and Noise was published in May 2017 in order to encourage better acoustic design for new residential schemes in order to protect future residents from the harmful effects of noise. This guidance can be seen as the missing link between the current NPPF and its predecessor, PPG24 (Planning Policy Guidance 24: Planning and Noise), which provided a prescriptive method for assessing sites for residential development, but without the nuance of ‘good acoustic design’ as outlined in ProPG.

ProPG allows the assessor to take a holistic approach to consider the site’s suitability, taking into consideration numerous design factors which previously may not have been considered alongside the noise level measured on site, for example the orientation of the building in relation to the main source of noise incident upon it.

It should be noted this document is not an official government code of practice, and neither replaces nor provides an authoritative interpretation of the law or government policy, and therefore should be seen as a good practice document only.

4.4 BS8233:2014

BS8233:2014 ‘*Sound insulation and noise reduction for buildings*’ describes recommended internal noise levels for residential spaces. These levels are shown in Table 4.1.

Activity	Location	07:00 to 23:00	23:00 to 07:00
Resting	Living Rooms	35 dB(A)	-
Dining	Dining Room/area	40 dB(A)	-
Sleeping (daytime resting)	Bedrooms	35 dB(A)	30 dB(A)

Table 4.1 BS8233 recommended internal background noise levels

It should be noted that the recommended internal noise levels outlined above are not applicable under “purge ventilation” conditions as defined by Approved Document F of the Building Regulations, as this should only occur occasionally (e.g. to remove odour from painting or burnt food). However, the levels above should be achieved whilst providing sufficient background ventilation, either via passive or mechanical methods.

The external building fabric would need to be carefully designed to achieve these recommended internal levels.

In addition to guidance on internal levels, BS8233:2014 also states the following with regards to noise within external amenity spaces:

‘For traditional external areas that are used for amenity space, such as gardens and patios, it is desirable that the external noise level does not exceed 50 dB $L_{Aeq,T}$, with an upper guideline value of 55 dB $L_{Aeq,T}$, which would be acceptable in noisier environments. However, it is also recognized that these guideline values are not achievable in all circumstances where development might be desirable. In higher noise areas, such as city centres or urban areas adjoining the strategic transport network, a compromise between elevated noise levels and other factors, such as the convenience of living in these locations or making efficient use of land resources to ensure development needs can be met, might be warranted. In such a situation, development should be designed to achieve the lowest practicable levels in these external amenity spaces, but should not be prohibited.’

As outlined above, the resulting noise levels in external amenity areas should not be a reason for refusal, providing that the noise levels are designed to be as low as practically possible within external amenity areas.

Expected levels within the proposed external amenity areas are outlined in Section 7.0 in more detail.

4.5 Approved Document O (ed. 2021)

Approved Document O (ADO) supports Part O of Schedule 1 to the Building Regulations 2010. ADO introduces requirements for residential premises in order to prevent overheating from occurring. There are two specific requirements from ADO:

Requirement O1 (1):

To limit unwanted solar gains in summer and to provide adequate means to remove heat from the indoor environment.

Requirement O1 (2):

- (a) Account must be taken of the safety of the occupant, and their reasonable enjoyment of the residence.
- (b) Mechanical cooling may only be used where sufficient heat cannot be removed from the indoor environment without it.

The statutory guidance to support Requirement O1(2)(a) contains requirements relating to noise at night.

4.5.1 Application

The guidance within ADO applies to new residential buildings only and are defined within the following table:

Title	Purpose for which the building is intended to be used.
Residential (dwellings)	Dwellings, which includes both dwellinghouses and flats.
Residential (institutions)	Home, school or other similar establishment, where people sleep on the premises. The building may be living accommodation for the care or maintenance of any of the following. A. Older and disabled people, due to illness or other physical or mental condition. B. People under the age of 5 years.
Residential (other)	Residential college, hall of residence and other student accommodation, and living accommodation for children ages 5 years or older.

Table 4.2 Residential buildings within the scope of ADO (ref. Table 0.1 of Approved Document O)

Paragraphs 3.2 and 3.3 of ADO specifically refer to noise within bedrooms at night. Whilst any habitable room could be used as a bedroom, it is proposed that the scope is confined to those rooms specifically designated as bedrooms.

4.5.2 Internal Noise Level Targets

ADO sets internal noise level targets within Paragraph 3.3 of the document:

“Windows are likely to be closed during sleeping hours if noise within bedrooms exceeds the following limits.

- a. 40dB $L_{Aeq,T}$ averaged over 8 hours (between 11pm and 7am)*
- b. 55dB L_{AFmax} more than 10 times a night (between 11pm and 7am).”*

Where an openable window for the removal of excess heat is predicted to result in the above internal noise levels to be exceeded, then the overheating mitigation strategy must adopt one of the alternative means listed within Paragraph 2.10 of ADO (presented within Section 4.7.3 of this report). This constraint applies regardless of which method is used to demonstrate compliance with Requirement O1 (1).

4.5.3 Methods to Remove Excess Heat

Paragraph 2.10 of ADO lists the means for removing excess heat from dwellings according to the following:

- Openable windows
- Ventilation louvres in external walls
- A mechanical ventilation system
- A mechanical cooling system

5.0 EXTERNAL BUILDING FABRIC SPECIFICATION

Sound reduction performance calculations have been undertaken in order to specify the minimum performance required from glazed and non-glazed elements in order to achieve the recommended internal noise levels shown in Table 4.1, taking into account average noise levels monitored during the environmental noise survey.

Please note that the glazed and non-glazed element calculations would need to be finalised once all design proposals are finalised.

5.1 Non-Glazed Elements

At this project stage, the exact construction of the non-glazed external building fabric is unknown, however, it is understood that it would be based upon the construction proposed in Table 5.1 and would be expected to provide the minimum figures shown above when tested in accordance with BS EN ISO, 140-3:1995.

Element	Octave band centre frequency SRI, dB					
	125Hz	250Hz	500Hz	1kHz	2kHz	4kHz
Brickwork Cavity Wall	41	43	48	50	55	55

Table 5.1 Assumed sound reduction performance for non-glazed elements

5.2 Glazed Elements

Minimum octave band sound reduction index (SRI) values required for all glazed elements to be installed are shown in Table 5.2. The performance is specified for the whole window unit, including the frame and other design features such as the inclusion of trickle vents. Sole glass performance data would not demonstrate compliance with this specification.

Glazing performance calculations have been based both on average measured night-time noise levels. The combined most robust results of these calculations are shown in Table 5.2.

Elevation	Octave band centre frequency SRI, dB						$R_w(C;C_{tr})$, dB
	125Hz	250Hz	500Hz	1kHz	2kHz	4kHz	
All elevations	27	29	36	41	42	52	39 (-1;-4)

Table 5.2 Required glazing performance

The nominated glazing supplier should verify that their proposed window system meets the attenuation figures shown at each centre frequency band as shown in Table 5.2.

Example glazing types that would be expected achieve the above spectral values are shown in Table 5.3.

Elevation	Example glazing type
All elevations	10/12/6.4mm

Table 5.3 Example glazing types

All major building elements should be tested in accordance with BS EN ISO 140-3:1995.

Independent testing at a UKAS accredited laboratory will be required in order to confirm the performance of the chosen system for an 'actual' configuration.

6.0 VENTILATION AND OVERHEATING

6.1 Ventilation Strategy

Based on the noise levels measured on site, appropriate ventilation systems are outlined in Table 6.1 below in order to ensure the internal noise environment is not compromised.

Ventilation System	Whole Dwelling Ventilation	Extract Ventilation
ADF System 1	Trickle vents providing a minimum performance of 43dB $D_{n,e,w}$	Intermittent extract fans
ADF System 3	Continuous mechanical extract (low rate) and trickle vents for supply providing a minimum performance of 43dB $D_{n,e,w}$	Continuous mechanical extract (high rate) with trickle vents providing inlet air
ADF System 4	Continuous mechanical supply and extract (low rate)	Continuous mechanical supply and extract (high rate)

Table 6.1 Ventilation systems

Where trickle vents are proposed, a typical number has been assumed based on the room size and number of windows. As trickle vents introduce a weak point in the building façade, it

should be noted that increasing the number of trickle vents will reduce the composite performance of the facade. If more trickle vents are required, the required insulation should be increased by '+10*LOG(N)' where N is the number of vents proposed. If trickle vents are proposed, the total number of trickle vents for each sensitive space should be confirmed so that calculations can be accurately revised.

In the case of mechanical ventilation, systems should be designed to meet the internal noise levels as defined in CIBSE Guide A (2015), as shown in Table 6.2.

Room Type	L _{Aeq} , dB	NR
Bedrooms	30	25
Living Rooms	35	30
Kitchen	45-50	40-45

Table 6.2 CIBSE Guide A 2015 guidance levels for mechanical building services

In all cases, purge ventilation would be provided by openable windows. As outlined in Section 4.4, the internal noise level requirement would not be applicable during purge conditions as this would only occur occasionally.

6.2 Openable Windows

Approved Document O (ADO) only applies to Bedrooms during night. The advice within this section would therefore only apply to Bedrooms during night-time hours (23:00-07:00) to ensure that the internal noise level targets of 40dB(A) L_{eq,T} and 55dB(A) L_{max} are not exceeded.

Table 6.3 and Figure 6.1 present the open area of the window as a % of the floor area which would need to be achieved to ensure that sufficient attenuation is provided from outside to inside.

Elevation	Maximum Open Area of the Window as a Percentage of the Floor Area to Achieve ADO Target Internal Noise Levels			
	Ground Floor	First Floor	Second Floor	Third Floor
	1%	1%	1%	1%
	0%	0%	1%	1%
	2%	2%	3%	3%

Table 6.3 Window open areas



Figure 6.1 Acoustic markup of window open areas

The overheating model should inform the design team whether the % open areas above would be sufficient to remove excess heat. In the event they are insufficient, other options to limit solar gains into the building should be investigated (such as those outlined in Section 2.7 of Approved Document O), or other means of removing excess heat should be explored (as outlined in Section 2.10 of the Approved Document).

Note: Acoustic open area is the measurable, cross-sectional, geometric area of an opening. For a partially open window, this is considered to be the lesser of either the size of the hole in the window frame that is left by the opening light, or the combined cross-sectional area around the opening light through which air must pass to move from outside to inside. The area around a hinged opening light includes the triangular areas on the sides adjacent to the hinge, and the rectangular area on the side opposite the hinge. This should not be used for comparing the air-flow performance of elements because this will also be dependent on factors such as depth (length of air-path), surface roughness and tortuosity.

6.3 Overheating Control Strategies

Where the open areas specified above are not sufficient for controlling overheating, then one or more of the following strategies will need to be adhered to:

- Fixed shading devices comprising any of the following:
 - Shutters
 - External blinds
 - Overhangs
 - Awnings
- Glazing design, involving any of the following solutions

- Size
- Orientation
- G-value
- Building design, e.g. the placement of balconies
- Shading provided by adjacent buildings structures or landscaping.
- Ventilation louvres in external walls
- A mechanical ventilation system
- A mechanical cooling system

An overheating assessment has been undertaken by Integration Consultancy Limited taking into consideration the acoustic restrictions outlined within this report, the percentage open area of the windows stated in Table 6.3, during the night-time period (23:00-07:00). The results of the assessment have concluded that Approved Document O overheating requirements are satisfied provided that the recommendations/ guidance within the Overheating Analysis (Part O) report by Integration Consultancy Limited is followed.

KP Acoustics have reviewed the proposed overheating strategy provided by Integration Consultancy Limited and are satisfied that the recommendations within the report adhere to the internal noise level target requirements of Approved Document O.

7.0 EXTERNAL AMENITY AREA ASSESSMENT

External amenity areas are proposed for all units except the two that face onto the main high street. These comprise ground floor external amenity areas and inset balconies on the upper levels.

The noise levels measured which are representative of these areas are 57dBA and 54dBA for daytime and night-time periods, respectively. The measured daytime noise levels in these areas do not meet the BS8233:2014 target guidance for noise in external amenity areas. However, the measured night-time noise levels in these areas meets the BS8233:2014 target guidance for noise in external amenity areas. The following should be noted:

Noise levels at ground floor level, first floor and second floor along the northern façade should be lower than those measured due to screening from the neighbouring buildings.

BS8233:2014 guidance states:

“it is also recognized that these guideline values are not achievable in all circumstances where development might be desirable. In higher noise areas, such as city centres or urban areas

adjoining the strategic transport network, a compromise between elevated noise levels and other factors, such as the convenience of living in these locations or making efficient use of land resources to ensure development needs can be met, might be warranted. In such a situation, development should be designed to achieve the lowest practicable levels in these external amenity spaces, but should not be prohibited”

Furthermore, residents will have access to large communal areas on the ground floor, which are predicted to achieve ambient noise levels below the BS8233:2014 upper guideline value of 55dB $L_{Aeq,T}$. Therefore, the above noise levels would be considered suitable for external amenity areas.

8.0 DIRECT NOISE TRANSFER ASSESSMENT

8.1 Party Floor System – Car Park to Ground Floor Residential

It is understood that the proposed party floor system separating the Basement Car-Park and the Ground Floor residential flats is as follows:

From bottom to top:

- 350mm Concrete Slab
- 350mm insulation
- 75mm floor finish

We have calculated the acoustic performance of the proposed party floor system separating the Basement Car-Park and the Ground Floor residential flats. The results of our assessment have concluded that the proposed floor system should provide sufficient acoustic performance and will satisfy Building Regulations.

8.2 Party Floor System – Retail Unit to Ground Floor Residential

It is understood that the proposed party floor system separating the Retail Unit and the Ground Floor residential flats is as follows:

From bottom to top:

- 62.5mm ceiling
- 200mm services void
- 250mm Concrete Slab
- 400mm insulation
- 75mm floor finish;

We have calculated the acoustic performance of the proposed party floor system separating the Retail Unit and the Ground Floor residential flats. The results of our assessment have concluded that the proposed floor system should provide sufficient acoustic performance and will satisfy Building Regulations.

9.0 PLANT NOISE ASSESSMENT

9.1 Proposed Plant Installations

The exact plant items and external building fabric are yet to be finalised. Therefore, we have undertaken our assessment based on the information provided at the time of writing the report.

It is understood that the proposed plant installation is comprised of the following:

At Roof Level:

- 29 No. Ecodan R32 Monobloc Air Source Heat Pumps (Rooftop)
- 19 No. Ecodan R32 Monobloc Air Source Heat Pumps (Third Floor Roof)

At Podium Level (Ground Floor):

- Standby Smoke Extract Fan (To be Specified)
- Condenser Unit(s) (To be Specified)
- Extract/ intake Fan (To be Specified)

Car Park Level (Lower Ground Floor):

- Extract / intake Fan (To be Specified)
- Generator (To be Specified)

The sound power level, as provided by the manufacturer, for each individual Ecodan R32 Monobloc air source heat pump is **58 dBA L_{WA}**.

9.2 Noise Assessment Guidance

We understand that Hitchin is under the jurisdiction of Hertfordshire County Council, of which does not specify noise criteria in relation to items of fixed mechanical plant. Therefore, we have used BS4142:2014 to set noise limits for the external mechanical plant associated with the development.

Table 9.1 presents the noise limits for mechanical plant based on the existing background noise levels measured during the survey.

Time Period	Maximum Plant Noise Emissions Criterion at Nearest Residential Receptor
Daytime (07:00-23:00)	≤51 dB(A)
Night-time (23:00-07:00)	≤45 dB(A)

Table 9.1 Proposed noise emissions criterion

9.3 Plant Limiting Noise Levels

At the time of writing the report the exact plant items and external building fabric are yet to be proposed. We have therefore specified limiting noise levels to be achieved for items of plant. Provided that the plant is selected and mitigated (where necessary) to achieve the limiting noise levels, the resultant plant noise emissions would be in line with the requirements of the Local Authority.

Table 9.2 presents the maximum noise levels to be achieved when measured at 3m from the outside of the Ground Floor (Podium) plantroom, and when measured at 3m outside the Lower Ground floor generator and intake/ extract louvres. Suitable acoustic attenuation such as acoustic enclosures, attenuators and louvres are likely to be required in order to achieve the noise limits set out below. We would expect the external building fabric to also provide attenuation. Therefore, when the plant items and the external building fabric of the development have been specified, a more detailed assessment should be undertaken.

Location	Descriptor	Octave Frequency Band (Hz)								Overall (dBA)
		63	125	250	500	1k	2k	4k	8k	
Ground Floor (Podium) EXT. Retail Plant	Sound Pressure Level @ 3m (dBA)	65	55	56	53	49	45	39	34	54
Car Park (Lower Ground Floor) Generator	Sound Pressure Level @3m (dBA)	63	50	44	37	35	29	30	-	42
Car Park (Lower Ground Floor) Intake / Extract Fan	Sound Pressure Level @3m (dBA)	-	26	30	35	33	42	28	17	44

Table 9.2 Maximum noise emissions criterion

9.4 Suitable Suppliers

We would recommend the following suppliers of the aforementioned attenuation:

- Environmental Equipment Corporation
- IAC
- Noico Ltd
- Waterloo Acoustics
- Allaway Acoustics
- Wakefield Acoustics
- Environ
- Caice

9.5 Anti-Vibration Mounting Strategy

In the case of all plant units, appropriate anti-vibration mounts should be installed in order to ensure that vibrations do not give rise to structure-borne noise. Appendix C outlines detailed advice in order to ensure that the system installer selects the appropriate anti-vibration mount for the installation.

It is the supplier's responsibility to ensure that all mountings offered are suitable for the loads, operating and environmental conditions which will prevail.

10.0 NOISE PROPAGATION MODEL

10.1 Noise Sensitive Receivers

An assessment of the cumulative noise from all plant running simultaneously has been undertaken to predict the cumulative noise levels at the nearest noise sensitive receptors.

Descriptor	Location Description
Nearest noise sensitive receptors (NSR1)	Rear façades. Residential block of flats, Latchmore Court to the north-west
Nearest noise sensitive receptors (NS2)	Rear façades. Residential block of flats, Poppy House to the north-west.
Nearest noise sensitive receptors (NSR3)	Rear façades. First Floor windows. Residential house to the north.
Nearest noise sensitive receptors (NSR4)	Front and rear facades. Block 3-4 Ground Floor Flats of the development itself.

Table 10.1 Nearest noise sensitive receptors descriptions




Figure 10.1 Noise model – Plant noise assessment

It can be seen that the predicted cumulative noise levels from all mechanical plant items running simultaneously achieve the noise limits set out in Section 9.2, provided that the recommendations within this report are followed.

10.2 Emergency Plant - Standby Smoke Extract (Ground Floor)

It is understood that Hitchin and Hertfordshire County Council do not have specific requirements for noise emitted from emergency plant or an emergency life supporting generators. We have therefore used guidance provided by the London Borough of Camden Council concerning emergency operating plant items to determine a suitable criterion for the Standby Smoke Extract Fan. The London Borough of Camden Council state the following regarding emergency equipment:

“Emergency equipment such as generators / Standby smoke extract which are only to be used for short periods of time will be required to meet the noise criteria of no more than 10dB above the background level ($L_{90, 15 \text{ min}}$). During standby periods, emergency equipment will be required to meet the usual criteria for plant and machinery. Conditions to this effect may be imposed in instances where emergency equipment forms part of the application.”

Please note the following:

Testing of any emergency plant should only be carried out during the daytime period (09:00-23:00). As testing of the emergency plant is likely to occur, at most, once a month and for a short period of time, it is our professional opinion that this would not cause adverse impact on the nearest noise sensitive receptors.

11.0 CONCLUSION

An environmental noise survey has been undertaken at 9-10 Hitchin High Street allowing the assessment of daytime and night-time levels likely to be experienced by the proposed development.

Measured noise levels allowed a robust glazing specification to be proposed which would provide internal noise levels for all residential environments of the development commensurate to the design range of BS8233:2014.

No further mitigation measures should be required in order to protect the proposed habitable spaces from external noise intrusion.

The maximum openable area for habitable room windows of the development have been presented based upon the requirements of Approved Document O.

KP Acoustics have reviewed the proposed overheating strategy provided by Integration Consultancy Limited and are satisfied that the recommendations within the report adhere to the internal noise level target requirements of Approved Document O.

Manufacturer's noise data as well as typical noise data for the proposed plant units have been used to set limiting noise levels for the future proposed plant items so as to comply with the noise emissions criteria, set out in Section 9.2, for compliance with Hertfordshire County Council requirements.

The cumulative noise level due to all plant running simultaneously was compared with the representative background noise level to assess the likelihood of impact considering the environmental noise context of the area.

The predicted noise levels from the proposed units should meet the requirements set out within this report, provided that the recommendations within this report are implemented.

A specific noise impact assessment will need to be undertaken once the proposed plant items have been finalised.

Hitchin High Street - Position 1
Environmental Time History
11/01/2023 to 12/01/2023




Figure 25713.TH1

Hitchin High Street - Position 2
Environmental Time History
11/01/2023 to 12/01/2023




Figure 25713.TH2

Hitchin High Street - Position 1
Representative Daytime Background Noise Level
11/01/2023 to 12/01/2023




Figure 25713.Daytime L90.TH1

Hitchin High Street - Position 2
Representative Daytime Background Noise Level
11/01/2023 to 12/01/2023




Figure 25713.Daytime L90.TH2

Hitchin High Street - Position 1
Representative Night-time Background Noise Level
11/01/2023 to 12/01/2023




Figure 25713.Night-time L90.TH1

Hitchin High Street - Position 2
Representative Night-time Background Noise Level
11/01/2023 to 12/01/2023




Figure 25713.Night-time L90.TH2

GENERAL ACOUSTIC TERMINOLOGY

Decibel scale - dB

In practice, when sound intensity or sound pressure is measured, a logarithmic scale is used in which the unit is the 'decibel', dB. This is derived from the human auditory system, where the dynamic range of human hearing is so large, in the order of 10^{13} units, that only a logarithmic scale is the sensible solution for displaying such a range.

Decibel scale, 'A' weighted - dB(A)

The human ear is less sensitive at frequency extremes, below 125Hz and above 16Khz. A sound level meter models the ears variable sensitivity to sound at different frequencies. This is achieved by building a filter into the Sound Level Meter with a similar frequency response to that of the ear, an A-weighted filter where the unit is dB(A).

L_{eq}

The sound from noise sources often fluctuates widely during a given period of time. An average value can be measured, the equivalent sound pressure level L_{eq} . The L_{eq} is the equivalent sound level which would deliver the same sound energy as the actual fluctuating sound measured in the same time period.

L_{10}

This is the level exceeded for no more than 10% of the time. This parameter is often used as a "not to exceed" criterion for noise.

L_{90}

This is the level exceeded for no more than 90% of the time. This parameter is often used as a descriptor of "background noise" for environmental impact studies.

L_{max}

This is the maximum sound pressure level that has been measured over a period.

Octave Bands

In order to completely determine the composition of a sound it is necessary to determine the sound level at each frequency individually. Usually, values are stated in octave bands. The audible frequency region is divided into 11 such octave bands whose centre frequencies are defined in accordance with international standards. These centre frequencies are: 16, 31.5, 63, 125, 250, 500, 1000, 2000, 4000, 8000 and 16000 Hertz.

Environmental noise terms are defined in BS7445, *Description and Measurement of Environmental Noise*.

APPLIED ACOUSTIC TERMINOLOGY

Addition of noise from several sources

Noise from different sound sources combines to produce a sound level higher than that from any individual source. Two equally intense sound sources operating together produce a sound level which is 3dB higher than a single source and 4 sources produce a 6dB higher sound level.

Attenuation by distance

Sound which propagates from a point source in free air attenuates by 6dB for each doubling of distance from the noise source. Sound energy from line sources (e.g. stream of cars) drops off by 3dB for each doubling of distance.

Subjective impression of noise

Hearing perception is highly individualised. Sensitivity to noise also depends on frequency content, time of occurrence, duration of sound and psychological factors such as emotion and expectations. The following table is a guide to explain increases or decreases in sound levels for many scenarios.

Change in sound level (dB)	Change in perceived loudness
1	Imperceptible
3	Just barely perceptible
6	Clearly noticeable
10	About twice as loud

Transmission path(s)

The transmission path is the path the sound takes from the source to the receiver. Where multiple paths exist in parallel, the reduction in each path should be calculated and summed at the receiving point. Outdoor barriers can block transmission paths, for example traffic noise. The effectiveness of barriers is dependent on factors such as its distance from the noise source and the receiver, its height and construction.

Ground-borne vibration

In addition to airborne noise levels caused by transportation, construction, and industrial sources there is also the generation of ground-borne vibration to consider. This can lead to structure-borne noise, perceptible vibration, or in rare cases, building damage.

Sound insulation - Absorption within porous materials

Upon encountering a porous material, sound energy is absorbed. Porous materials which are intended to absorb sound are known as absorbents, and usually absorb 50 to 90% of the energy and are frequency dependent. Some are designed to absorb low frequencies, some for high frequencies and more exotic designs being able to absorb very wide ranges of frequencies. The energy is converted into both mechanical movement and heat within the material; both the stiffness and mass of panels affect the sound insulation performance.

ANTI-VIBRATION MOUNTING SPECIFICATION REFERENCE DOCUMENT

1.0 General

- 1.1 All mountings shall provide the static deflection, under the equipment weight, shown in the schedules. Mounting selection should allow for any eccentric load distribution or torque reaction, so that the design deflection is achieved on all mountings under the equipment, under operating conditions.
- 1.2 It is the supplier's responsibility to ensure that all mountings offered are suitable for the loads, operating and environmental conditions which will prevail. Particular attention should be paid to mountings which will be exposed to atmospheric conditions to prevent corrosion.
- 1.3 All mountings shall be colour coded, or otherwise marked, to indicate their load capacity, to facilitate identification during installation.

Where use of resilient supports allows omission of pipe flexible connections for vibration/noise isolation, it shall be the Mechanical Service Consultant's or Contractor's responsibility to decide whether such devices are required to compensate for misalignment or thermal strain.

2.1 Type A Mounting (Caged Spring Type)

- 2.1.1 Each mounting shall consist of cast or fabricated telescopic top and bottom housings enclosing one or more helical steel springs as the principle isolation elements, and shall incorporate a built-in levelling device. The housing should be designed to permit visual inspection of the springs after installation, i.e. the spring must not be totally enclosed.
- 2.1.2 The springs shall have an outside diameter of not less than 75% of the operating height, and be selected to have at least 50% overload capacity before becoming coil-bound.
- 2.1.3 The bottom plate of each mounting shall have bonded to it a rubber/neoprene pad designed to attenuate any high frequency energy transmitted by the springs.
- 2.1.4 Mountings incorporating snubbers or restraining devices shall be designed so that the snubbing, damping or restraining mechanism is capable of being adjusted to have no significant effect during the normal running of the isolated machine.
- 2.1.5 All nuts, bolts or other elements used for adjustment of a mounting shall incorporate locking mechanisms to prevent the isolator going out of adjustment as a result of vibration or accidental or unauthorised tampering.

2.2 Type B Mounting (Open Spring Type)

- 2.2.1 Each mounting shall consist of one or more helical steel springs as the principal isolation elements, and shall incorporate a built-in levelling device.
- 2.2.2 The springs shall be fixed or otherwise securely located to cast or fabricated top and bottom plates, shall have an outside diameter of not less than 75% of the operating height, and shall be selected to have at least 50% overload capacity before becoming coil-bound.
- 2.2.3 The bottom plate shall have bonded to it a rubber/ neoprene pad designed to attenuate any high frequency energy transmitted by the springs.

2.3 Type C Mounting (Rubber/Neoprene Type)

Each mounting shall consist of a steel top plate and base plate completely embedded in oil resistant rubber/neoprene. Each mounting shall be capable of being fitted with a levelling device, and should have bolt holes in the base plate and a threaded metal insert in the top plate so that they can be bolted to the floor and equipment where required.

3.0 Plant Bases

3.1 Type A Bases (A.V. Rails)

An A.V. Rail shall comprise a steel beam with two or more height-saving brackets. The steel sections must be sufficiently rigid to prevent undue strain in the equipment and if necessary should be checked by the Structural Engineer.

3.2 Type B Bases (Steel Plant Bases)

Steel plant bases shall comprise an all-welded steel framework of sufficient rigidity to provide adequate support for the equipment, and fitted with isolator height saving brackets. The frame depth shall be approximately 1/10 of the longest dimension of the equipment with a minimum of 150 mm. This form of base may be used as a composite A.V. rail system.

3.3 Type C Bases (Concrete Inertia Base: for use with steel springs)

These shall consist of an all-welded steel pouring frame-work with height saving brackets, and a frame depth of approximately 1/12 of the longest dimension of the equipment, with a minimum of 100 mm. The bottom of the pouring frame should be blanked off, and concrete (2300 kg/m³) poured in over steel reinforcing rods positioned 35 mm above the bottom. The inertia base should be sufficiently large to provide support for all parts of the equipment, including any components which over-hang the equipment base, such as suction and discharge elbows on centrifugal pumps.