FAO – Sam Dicocco
Ref – 18/00968/FP
Proposal – Erection of 1no. three bedroom, 1no. two bedroom semi detached dwellings, with provision of on site car parking and associated ancillary works
Location – Land adjacent to 26 Morton Street, Royston, Hertfordshire

Thank you for your letter of 19 April 2018 providing Network Rail with an opportunity to comment on the abovementioned application.

With reference to the protection of the railway, Network Rail has no objection in principle to the development, but below are some requirements which must be met, especially with the close proximity to the development of an electrified railway.

Drainage
All surface and foul water arising from the proposed works must be collected and diverted away from Network Rail property. In the absence of detailed plans all soakaways must be located so as to discharge away from the railway infrastructure.

Fail Safe Use of Crane and Plant
All operations, including the use of cranes or other mechanical plant working adjacent to Network Rail's property, must at all times be carried out in a "fail safe" manner such that in the event of mishandling, collapse or failure, no materials or plant are capable of falling within 3.0m of the nearest rail of the adjacent railway line, or where the railway is electrified, within 3.0m of overhead electrical equipment or supports.

Excavations/Earthworks
All excavations/ earthworks carried out in the vicinity of Network Rail property/ structures must be designed and executed such that no interference with the integrity of that property/ structure can occur. If temporary works compounds are to be located adjacent to the operational railway, these should be included in a method statement for approval by Network Rail. Prior to commencement of works, full details of excavations and earthworks to be carried out near the railway undertaker's boundary fence should be submitted for the approval of the Local Planning Authority acting in consultation with the railway undertaker and the works shall only be carried out in accordance with the approved details. Where development may affect the railway, consultation with the Asset Protection Project Manager should be undertaken. Network Rail will not accept any liability for any settlement, disturbance or damage caused to any development by failure of the railway infrastructure nor for any noise or vibration arising from the normal use and/or maintenance of the operational railway. No right of support is given or can be claimed from Network Rails infrastructure or railway land.

Security of Mutual Boundary
Security of the railway boundary will need to be maintained at all times. If the works require temporary or permanent alterations to the mutual boundary the applicant must contact Network Rail's Asset Protection Project Manager.

Armco Safety Barriers
An Armco or similar barrier should be located in positions where vehicles may be in a position to drive into or roll onto the railway or damage the lineside fencing. Network Rail's existing fencing / wall must not be removed or damaged. Given the considerable number of vehicle movements likely provision should be made at each turning area/roadway/car parking area adjacent to the railway. This is in accord with the new guidance for road/rail vehicle incursion NR/LV/CIV/00012 following on from DfT advice issued in 2003, now updated to include risk of incursion from private land/roadways.

Fencing
Because of the nature of the proposed developments we consider that there will be an increased risk of trespass onto the railway. The Developer must provide a suitable trespass proof fence adjacent to Network Rail's boundary (minimum approx. 1.8m high) and make provision for its future maintenance and renewal. Network Rail's existing fencing / wall must not be removed or damaged.

Method Statements/Fail Safe/Possessions

Method statements may require to be submitted to Network Rail's Asset Protection Project Manager at the below address for approval prior to works commencing on site. This should include an outline of the proposed method of construction, risk assessment in relation to the railway and construction traffic management plan. Where appropriate an asset protection agreement will have to be entered into. Where any works cannot be carried out in a "fail-safe" manner, it will be necessary to restrict those works to periods when the railway is closed to rail traffic i.e. "possession" which must be booked via Network Rail's Asset Protection Project Manager and are subject to a minimum prior notice period for booking of 20 weeks. **Generally if excavations/piling/buildings are to be located within 10m of the railway boundary a method statement should be submitted for NR approval.**

Demolition/felling of trees

Any demolition or refurbishment works must not be carried out on the development site that may endanger the safe operation of the railway, or the stability of the adjoining Network Rail structures. The demolition of buildings or other structures or felling of trees near to the operational railway infrastructure (especially in this location where high voltage overhead lines are present) must be carried out in accordance with an agreed method statement. Approval of the method statement must be obtained from Network Rail's Asset Protection Project Manager before the development can commence.

ENCROACHMENT

The developer/applicant must ensure that their proposal, both during construction, and after completion of works on site, does not affect the safety, operation or integrity of the operational railway, Network Rail and its infrastructure or undermine or damage or adversely affect any railway land and structures. There must be no physical encroachment of the proposal onto Network Rail land, no over-sailing into Network Rail air-space and no encroachment of foundations onto Network Rail land and soil. There must be no physical encroachment of any foundations onto Network Rail land. Any future maintenance must be conducted solely within the applicant's land ownership. Should the applicant require access to Network Rail land then must seek approval from the Network Rail Asset Protection Team. Any unauthorised access to Network Rail land or air-space is an act of trespass and we would remind the council that this is a criminal offence (**s55 British Transport Commission Act 1949**). Should the applicant be granted access to Network Rail land then they will be liable for all costs incurred in facilitating the proposal.

Noise/Soundproofing

The Developer should be aware that any development for residential use adjacent to an operational railway may result in neighbour issues arising. Consequently every endeavour should be made by the developer to provide adequate soundproofing for each dwelling. Please note that in a worst case scenario there could be trains running 24 hours a day and the soundproofing should take this into account.

Lighting

Where new lighting is to be erected adjacent to the operational railway the potential for train drivers to be dazzled must be eliminated. In addition the location and colour of lights must not give rise to the potential for confusion with the signalling arrangements on the railway. Detail of any external lighting should be provided as a condition if not already indicated on the application.

Access to Railway

All roads, paths or ways providing access to any part of the railway undertaker's land shall be kept open at all times during and after the development.

Network Rail is required to recover all reasonable costs associated with facilitating these works.

I would advise that in particular the **boundary fencing, Armco barriers, method statements, soundproofing and lighting** should be the subject of conditions, the reasons for which can include the safety, operational needs and integrity of the railway. For the other matters we would be pleased if an informative could be attached to the decision notice.

I trust full cognisance will be taken in respect of these comments. If you have any further queries or require clarification of any aspects, please do not hesitate to contact myself I would also be grateful if you could inform me of the outcome of this application, forwarding a copy of the Decision Notice to me in due course.

The method statement will need to be agreed with:

Asset Protection Project Manager
Network Rail (London North Eastern)
Floor 3B
George Stephenson House
Toft Green
York
Y01 6JT